

DELHI DEVELOPMENT AUTHORITY

No.EM 1(10)83/ 5935

Dt., the 11th June, 1985.

C I R C U L A R NO 101

A number of cases of inadequate foundations and over-payment in respect of items of works pertaining to foundations have come to light. It is, therefore, ordered with immediate effect-

1. For Housing Schemes- the technical parameter viz. plinth level, formation level and depth of foundations should have the approval of the Chief Engineers.
- 2(a) AES will test check items of work pertaining to foundations-100%.
- (b) EEs will test check lean concrete under the foundations 100% and other items of foundation 25%.
- (c) The percentage of test check for items of super structure will remain as in force at present.
3. SEs will arrange their inspections in such a way that they cover all schemes of foundation stage at least once.
4. CEs should also arrange their inspections in such a way that they are satisfied that the technical parameters are enforced at site.

d

( J.K.Varshneya )  
Engineer Member.

11.6.85,

Copy to:-

1. All CEs.
2. All SES i/c SWS/Dir.(Hort).
3. All EEs i/c SWS/Dy.Directors(Hort).
4. All AES i/c ASWs/A.Ds(Hort).