

528

DELHI DEVELOPMENT AUTHORITY.  
(EM's Office).

No. EM. 1(10)83/4640

DATED: 25.3.91.

STANDING INSTRUCTIONS NO. 323.

Sub: Segregation of Quantities/lean concrete under  
floors & under walls  
.....

It has been observed that in some of the contracts, quantities of lean concrete (1:5:10)-(1 cement:5 fine sand: 10 graded stone aggregate 40mm nominal size) required to be laid under floors had been clubbed with the lean concrete (1:5:10- 1 cement: 5 coarse sand: 10 graded stone aggregate 40mm nominal size) required to be laid under walls and retaining walls etc. This resulted in increase in cost of the Dwelling Units.

All Chief Engineers/Superintending Engineers/ Executive Engineers(Field/Planning)are directed to ensure that such mix up is avoided.

(W. D. Dandage)  
Engineer Member.

W.D. Dandage  
27/3/91

Copy to:

1. All Chief Engineers.
2. All Suptdg. Engineers.
3. All Executive Engineers.