

DELHI DEVELOPMENT AUTHORITY
(ENGINEER MEMBER'S OFFICE)

No. EM.1(10)83/4146

Dated: 13.7.83

CIRCULAR NO. 33

Sub: Testing of Cement.

The Fact Finding Committee headed by Er. V.R.Vaish has recommended that all consignment of cement that are received in DDA should also be tested by Ex. Engineers, Store Divisions where cement is found to be below specification, matter should be taken up immediately with the cement controller.

It has been reported that this practice of testing of cement consignments has already been started and about 30 consignments have been tested so far. It has been decided that in future every consignment of cement should be got tested and wherever the cement is not up to the w mark, the matter is taken up with the supplier/cement controller/DGS&D etc.

The field officers/EEs/AEs/JEs are also requested not to accept any cement from Central Stores which is apparantly partially set or is of bad quality. The cement bags weighing less than 48 kgs. should also not be accepted and left in the stores.

These instructions must be followed strictly.

Sd/-
(K.D. BALI)
ENGINEER MEMBER