

DELHI DEVELOPMENT AUTHORITY
(ENGINEER MEMBER'S OFFICE)

NO.EM.1(10)83/4148

Dated: 13.7.83

CIRCULAR NO. 35

Sub: Holes left for scaffolding.

The Fact Finding Committee headed by Er.V.R.Vaish has reported that large holes are being left in brick work for scaffolding which is undesirable. They have further recommended that all brick masonry, cement mortar and cement concrete work should be cured with copious quantity of water for 7 to 10 days.

Holes for scaffolding should normally consist of one header only and should not be closer than 600mm apart and should not be provided at points of stress concentration. These should also be vertically above each other and should not be staggered as far as possible.

All Engineers are requested to ensure that these instructions are scrupulously followed in works being executed under their control.

d/-
(K.D. BALI)
ENGINEER MEMBER