

दिल्ली विकास प्राधिकरण
अधिशाषी अभियंता का कार्यालय
स्पोर्ट्स मैनेजमेंट सेल
1 मंजिल, स्कैश और बैडमिंटन स्टेडियम,
सिरी फोर्ट रोड, नई दिल्ली -110049 ईमेल: ee01smc@gmail.com

No. F I(477)EE/SMC/DDA/2019-20/ 714

Date : 23/01/2020

To

M/s S.V. Enterprises,
A-125, Surajmal Vihar,
Delhi-110092.

मैसर्स एस वी उद्यम,
ए -125, सूरजमल विहार,
दिल्ली- 110092

Sub : M/o Various sport complexes/Golf Courses. (A/R & M/O works at Maharaja Surajmal Stadium Nangloi for the year 2019-20)

विभिन्न खेल परिसरों / गोल्फ कोर्स का रखरखाव (ए/आर एंड एम/ओ वर्ष 2019-20 में महाराजा सूरजमल स्टेडियम के लिए काम)।

SH: Renovation of Guard room, repair of boundary wall i/c fixing of concertina coil along western wall and fixing of Retro-reflective boards at Maharaja Surajmal Stadium, Nangloi.

महाराजा सूरजमल स्टेडियम, नांगलोई में गार्ड रूम का नवीनीकरण, कंसर्टिना कॉइल को ठीक करने सहित बाउंड्री वॉल की मरम्मत, वेस्टर्न वॉल के साथ और रेट्रो-चिंतनशील बोर्डों को ठीक करना।

Ref:1. Performance guarantee amounting to Rs. 20,100/- vide FDR Account No. 34930300014241 dated 20.01.2020 valid upto 19.07.2020 issued by Bank of Baroda, Krishna Nagar, Delhi- 110051 submitted by you vide letter no. nil dated 20.01.2020.

निष्पादन गारंटी रुपये 20,100/- एफ डी आर खाता 34930300014241 दिनांक 20.01.2020 से 19.07.2020 तक मान्य, जारीकर्ता बैंक ऑफ बड़ौदा, कृष्णा नगर, दिल्ली- 110051 पत्र संख्या शून्य दिनांक 20.01.2020 आपके द्वारा प्रस्तुत की गई है।

2. This office letter of intent/acceptance of your tender issued vide no. F1(477)EE/SMC/DDA/2019-20/693 date 15.01.2020.

जारी किए गए अपने निविदा के इरादे / स्वीकृति का यह कार्यालय पत्र नं F1 (477) EE/ SMC/ DDA/ 2019-20 / 693 दिनांक 15.01.2020.

Sir,

Your Percentage rate tender for the above mentioned work has been accepted on behalf of the Delhi Development Authority as per the rates and conditions given below.

नीचे दी गई प्रतिशत दरों और शर्तों के अनुसार, दिल्ली विकास प्राधिकरण की तरफ से उपर्युक्त कार्य के लिए आपकी प्रतिशत दर निविदा स्वीकार करली गई है।

1. Estt. Cost/ अनुमानित लागत : Rs. 4,03,855/-
(Rs. Four lakh three thousand eight hundred fifty five only)
(रुपये चार लाख तीन हजार आठ सौ पचपन केवल)
2. Tendered /Quoted Amount : Rs. 4,23,482/-
(Rs. Four lakh twenty three thousand four hundred eighty two only)
(रुपये चार लाख तेईस हजार हजार चार सौ बयासी केवल)
3. Percentage/Quoted : 4.86 % Above

Contd.2.

4. Negotiated /Accepted Tendered Amount : Rs. 4,00,382/-
स्वीकृत निविदा/राशि : (Rs.Four lakh three hundred eighty two only)
(रुपये चार लाख तीन सौ बयासी केवल)
5. Negotiated Percentage : 0.86 % Below
6. Time allowed/ समय की अनुमति : 30 days (दिन)

The performance guarantee 5% of the tendered amount as FDR Account No. 34930300014241 dated 20.01.2020 amounting to Rs. 20,100/-(Rupees Twenty thousand one hundred only) valid upto 19.07.2020 issued by Bank of Baroda, Krishna Nagar, Delhi- 110051 Delhi- 110085 submitted by you, has been considered by the Competent Authority.

सक्षम प्राधिकारी द्वारा विचार किया गया है कि आपके द्वारा प्रस्तुत की गई निविदा राशि की 5% निष्पादन गारंटी के रूप में एफ डी आर खाता संख्या 34930300014241 दिनांक 20.01.2020 रुपये 20,100/- (रुपये बीस हजार एक सौ केवल) बैंक ऑफ बड़ौदा, कृष्णा नगर दिल्ली- 110051 जारी किए गए दिनांक 19.07.2020 तक वैध माना गया है।

You are requested to contact Assistant Engineer- III/SMC for taking possession of the site & start the work. You are also requested to attend this office along with non-judicial stamp paper worth Rs. 50/- to sign to complete the formal agreement within 7 days from the date of this letter. Your negotiated letter dated 17.12.2019 is not the part of the agreement.

आपसे अनुरोध है कि साइट पर कब्जा करने और काम शुरू करने के लिए सहायक अभियंता- III/ एसएमसी से संपर्क करें। आप से यह भी अनुरोध है कि आपको इस कार्यालय में इस पत्र के जारी होने की तारीख से 7 दिनों के भीतर गैर-न्यायिक 50रु/- के स्टैप पेपर के साथ-साथ औपचारिक समझौते पर हस्ताक्षर करने है। आपका समझौता पत्र दिनांक 17.12.2019 अनुबंध का हिस्सा बन गया है।

Please note that the time allowed for carrying out the work will be reckoned from the 10th days after the date of issue of this letter to commence the work. Further if you fail to commence the work as specified above, the award letter will be withdrawn by DDA without prejudice to any other right or remedy available on law will be at liberty to forfeit the Earnest Money and performance guarantee absolutely.

कृपया ध्यान दें कि काम करने के लिए अनुमति के समय को 'काम शुरू करने के लिए इस पत्र के जारी होने की तारीख के 10 दिनों के बाद से गिना जाएगा। इसके अलावा यदि आप ऊपर निर्दिष्ट कार्य शुरू करने में असफल हो जाते हैं, तो डीडीए द्वारा किसी भी अन्य अधिकार या कानून पर उपलब्ध उपायों के लिए पूर्वाग्रह से वापस ले लिया जाएगा अग्रिम धन राशि और प्रदर्शन गारंटी को पूरी तरह से ज़ब्त करने के लिए स्वतंत्र होगा।


Yours faithfully,
आपका विश्वसनीय,

अधिशाषी अभियंता
Executive Engineer,
एसएमसी / डीडीए
SMC/DDA

Copy to (प्रतिलिपि): -

1. Commissioner (Sports)/DDA.
आयुक्त (खेल) / डीडीए
2. Chief Engineer (Sports)DDA
मुख्य अभियंता (खेल) डीडीए

3. Project Director (Sports)/DDA.
परियोजना निदेशक (खेल) / डीडीए
4. Director (System) DDA .
निदेशक (सिस्टम) डीडीए
5. Executive Engineer/QAC-I/DDA
अधिशायी अभियंता / क्यूएसी- I / डीडीए
6. Dy. CAO (Sports)/DDA
उप. सीएओ (खेल) / डीडीए
7. Secy./Coordination.
सचिव।समन्वय
8. Secy/ /DDA.
सचिव / / डीडीए
9. Labour Commissioner, Rajpura Road, New Delhi.
श्रम आयुक्त, राजपुरा रोड, नई दिल्ली
10. Dy. Commr. Sales Tax Office Govt. of NCT Room No. 211, Bikri Kar Bhawan, ITO, New Delhi.
उप Commr बिक्री कर कार्यालय सरकार एनसीटी कमरा सं 211, बिक्री कर भवन, आई टी ओ, नई दिल्ली।
11. Trans Yamuna Contractor association (Regd) 11-12 Vir Sawakar Market (Budh Bazar) Gandhi Nagar, New Delhi-110031 (UPC).
यमुना ठेकेदार संघ (रजिग) 11-12 वीर सवाकर बाजार (बुध बाज़ार) गांधी नगर, नई दिल्ली -110031 (यूपीसी)।
12. Delhi Contractors Building association (Regd) No. 5503 Ch. Bhim Singh Road, Delhi (Ch. Prem Raj Bhawan New Chandrawal Road (UPC).
दिल्ली के ठेकेदार बिल्डिंग एसोसिएशन (पंजीकरण) सं। 5503 चा।भीम सिंह रोड, दिल्ली (चौ प्रेम राज भवन नई चंद्रावल रोड (यूपीसी)
13. Delhi Contractors Welfare Association (Regd) 306, Masjid Moth, South Extn. Part-II, New Delhi-110049 (UPC).
दिल्ली कन्स्ट्रक्टर्स वेलफेयर एसोसिएशन (रजिड) 306, मस्जिद माँथ, दक्षिण विस्तार भाग- II, नई दिल्ली -110049 (यूपीसी)
14. Indian Contractor Association (Regd) G-80/20, Main Bazar Laxmi Nagar, Delhi-110092 (UPC).
भारतीय ठेकेदार एसोसिएशन (रजिड) जी -80 / 20, मुख्य बाजार लक्ष्मी नगर, दिल्ली -110092 (यूपीसी)।
15. Assistant Engineer-III/SMC/DDA for information alongwith copy of schedule of quantities.
जानकारी के लिए सहायक अभियंता- III /एसएमसी/डीडीए, मात्रा के अनुसूची की प्रति के साथ।
16. Head Clerk SMC/ DDA. He is requested to issue the Master Register at once.
हेड क्लर्क एसएमसी/डीडीए उन्हें एक बार में मास्टर रजिस्टर जारी करने का अनुरोध किया जाता है।
17. Accountant/SMC/ DDA.
लेखाकार/एसएमसी / डीडीए
18. Copy of agreement.
समझौते की प्रतिलिपि
19. E-mail to ddatender@dda.org.in
ई-मेल को ddatender@dda.org.in
20. Guard file
गार्ड फ़ाइल


 अधिशायी अभियंता
 Executive Engineer,
 एसएमसी/डीडीए
 SMC/DDA

Percentage BoQ

Validate Print Help

Tender Inviting Authority: Executive Engineer/Sports Management Cell

Name of Work: M/o Various sport complexes/Golf Courses. (A/R & M/O works at Maharaja Surajmal Stadium Nangloi for the year 2019-20)

SH:Renovation of Guard room, repair of boundary wall i/c fixing of concertina coil along western wall and fixing of Retro-reflective boards at Maharaja Surajmal Stadium, Nangloi.

Estimated Cost : Rs. 4,03,855/-

NIT No: 18/NIT/AE(P)/ EE/SMC/DDA/2019-20

Bidder Name : M/s S.V. Enterprises


PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Rate	NUMBER # TOTAL AMOUNT	TEXT # TOTAL AMOUNT In Words
		4	5	6	53	55
1.00	Stone work (machine cut edges) for wall lining etc. (vener work) upto 10 metre height, backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand) including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : (To be secured to the backing and the sides by means of cramps and pins which shall be paid for separately) : a) Gang saw cut stone: 30mm thick Red sand stone	24.00	sqm	2360.10	56642.40	INR Fifty Six Thousand Six Hundred & Forty Two and Paise Forty Only
2.00	Fixing available sand stone for wall lining etc. (vener work) upto 10 metre height, backing filled with a grout of average 12 mm thick cement mortar 1:3 (1 cement : 3 coarse sand) including pointing in white cement mortar 1:2 (1 white cement : 2 stone dust) with an admixture of pigment matching the stone shade : (To be secured to the backing and the sides by means of cramps and pins which shall be paid for separately) : a) Gang saw cut stone: 30mm thick Red sand stone (i/c cost of collecting, cleaning etc. complete)	13.00	sqm	1700.65	22108.45	INR Twenty Two Thousand One Hundred & Eight and Paise Forty Five Only
3.00	Random rubble masonry with available hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand) (i/c cost of collecting, cleaning etc. complete)	1.00	cum	5360.45	5360.45	INR Five Thousand Three Hundred & Sixty and Paise Forty Five Only
4.00	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	83.00	kg	86.05	7142.15	INR Seven Thousand One Hundred & Forty Two and Paise Fifteen Only
5.00	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	486.00	kg	101.75	49450.50	INR Forty Nine Thousand Four Hundred & Fifty and Paise Fifty Only
6.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	570.00	sqm	79.95	45571.50	INR Forty Five Thousand Five Hundred & Seventy One and Paise Fifty Only
7.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm)	62.00	sqm	59.35	3679.70	INR Three Thousand Six Hundred & Seventy Nine and Paise Seventy Only

8.00	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shade.	93.00	sqm	49.55	4608.15	INR Four Thousand Six Hundred & Eight and Paise Fifteen Only
9.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.: 20 mm nominal outer dia Pipes.	15.00	metre	478.15	7172.25	INR Seven Thousand One Hundred & Seventy Two and Paise Twenty Five Only
10.00	Providing and fixing PTMT bib cock of approved quality and colour.: 15 mm nominal bore, 122mm long, weighing not less than 99 gms	3.00	each	162.05	486.15	INR Four Hundred & Eighty Six and Paise Fifteen Only
11.00	Providing and fixing PTMT stop cock of approved quality and colour. 15 mm nominal bore, 86 mm long, weighing not less than 88 gms	1.00	each	116.55	116.55	INR One Hundred & Sixteen and Paise Fifty Five Only
12.00	Providing and fixing uplasticised PVC connection pipe with brass unions: 45cm length 15mm nominal bore	2.00	each	83.00	166.00	INR One Hundred & Sixty Six Only
13.00	Welding by gas or electric plant including transportation of plant at site etc. complete.	500.00	cm	3.35	1675.00	INR One Thousand Six Hundred & Seventy Five Only
14.00	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 300x16 mm	5.00	each	183.30	916.50	INR Nine Hundred & Sixteen and Paise Fifty Only
15.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	2.00	cum	6157.45	12314.90	INR Twelve Thousand Three Hundred & Fourteen and Paise Ninety Only
16.00	15 mm cement plaster on rough side of single or half brick wall of mix: 1:4 (1 cement: 4 coarse sand)	10.00	sqm	318.95	3189.50	INR Three Thousand One Hundred & Eighty Nine and Paise Fifty Only
17.00	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	15.00	sqm	276.15	4142.25	INR Four Thousand One Hundred & Forty Two and Paise Twenty Five Only
18.00	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing of surplus excavated soil as directed with in a lead of 50 mm and lift upto 1.5 m. All kind of soil	10.00	each	26.45	264.50	INR Two Hundred & Sixty Four and Paise Fifty Only
19.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	1.00	cum	6788.60	6788.60	INR Six Thousand Seven Hundred & Eighty Eight and Paise Sixty Only
20.00	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) i/c fixing the railing with necessary of required size etc. complete as per approval of Engineer-in charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	170.00	kg	488.50	83045.00	INR Eighty Three Thousand & Forty Five Only

21.00	Manufacturing, supplying and fixing retro reflective signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge. (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment).					INR Fifty Nine Thousand Nine Hundred & Thirty Four and Paise Sixty Only
22.00	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	12.00	sqm	4994.55	59934.60	INR Twenty Nine Thousand & Eighty Only
23.00	Add 0% for cost index	100.00	metre	290.80	29080.00	
Total in Figures		403855.10	metre	0.00	0.00	INR Zero Only
Quoted Rate in Figures					403855.10	INR Four Lakh Three Thousand Eight Hundred & Fifty Five and Paise Ten Only
Quoted Rate in Words			Less (-)	0.86%	400381.95	INR Four Lakh Three Hundred & Eighty One and Paise Ninety Five Only
						INR Four Lakh Three Hundred & Eighty One and Paise Ninety Five Only


 अधिशासी अभियन्ता
 खेल प्रबंधन प्रकोष्ठ
 सिरि कोर्ट नई दिल्ली-110017
 23/11/2022
 23/01/2020