

दिल्ली विकास प्राधिकरण
अधिशाषी अभियंता का कार्यालय
स्पोर्ट्स मैनेजमेंट सेल
1 मंजिल, स्कैश और बैडमिंटन स्टेडियम,
सिरी फोर्ट रोड, नई दिल्ली -110049 ईमेल: ee01smc@gmail.com

No. F I(398)EE/SMC/DDA/2019-20/ 510

Date : 13/11/2019.

To

M/s Keertiman Builders,
54, Pocket- B, Near MIG Flat,
Mayur Vihar, Phase -III,
Delhi-110096.

मेसर्स कीर्तिमान बिल्डर्स,
54, पॉकेट- B, MIG फ्लैट के पास,
मयूर विहार, फेज- III,
दिल्ली-110096

Sub : M/o various Sport complexes/Golf Courses.(A/R & M/O works at Rohini Sports Complex for the year of 2019-20)

विभिन्न खेल परिसरों / गोल्फ कोर्स का रखरखाव (ए/आर एंड एम/ओ वर्ष 2019-20 में रोहिणी स्पोर्ट्स कॉम्प्लेक्स के लिए काम)।

SH: Providing and laying water proofing treatment over roof and renovation of change room by P/F new G.I. line, sanitary fitting, wall/floor tiles, granite stone flooring and other misc. work at swimming pool Rohini Sports Complex.

रोहिणी स्पोर्ट्स कॉम्प्लेक्स में छत के ऊपर वाटर प्रूफिंग ट्रीटमेंट प्रदान करना और बदलना और चेंज रूम का नवीनीकरण द्वारा नए जी.आई. लाइन, सैनिटरी फिटिंग, दीवार / फर्श टाइल्स, ग्रेनाइट पत्थर फर्श के कार्य और अन्य विविध काम ।

Ref:- Performance guarantee amounting to Rs. 75,100/- vide FDR A/c No. 606201644000053 dated 11.11.2019 valid upto 08.03.2020 issued by Vijaya Bank, 48, Pocket-2, Jasola, New Delhi- 110025 submitted by your vide letter no. nil dated 11.11.2019.

निष्पादन गारंटी रुपये 75,100/- एफ डी आर खाता संख्या 606201644000053 दिनांक 11.11.2019 से 08.03.2020 तक मान्य, जारीकर्ता विजया बैंक, 48, पॉकेट -2, जसोला, नई दिल्ली- 110025 पत्र संख्या शून्य दिनांक 11.11.2019 आपके द्वारा प्रस्तुत की गई है ।

Sir,

Your Percentage rate tender for the above mentioned work has been accepted on behalf of the Delhi Development Authority as per the rates and conditions given below.

नीचे दी गई प्रतिशत दरों और शर्तों के अनुसार, दिल्ली विकास प्राधिकरण की तरफ से उपर्युक्त कार्य के लिए आपकी प्रतिशत दर निविदा स्वीकार करली गई है।

1. Estt. Cost/ अनुमानित लागत : Rs. 24,21,975/-
(Rs. Twenty four lakh twenty one thousand nine hundred seventy five only)
(रुपये चौबीस लाख इक्कीस हजार नौ सौ पचहत्तर केवल)
2. Accepted Tendered /Amount स्वीकृत निविदा राशि : Rs. 15,01,867/-
(Rs. Fifteen lakh one thousand eight hundred sixty seven only)
(रुपये पंद्रह लाख एक हजार आठ सौ सत्सठ केवल)

Contd.2.

3. Percentage/ प्रतिशत : 37.99 % Below

4. Time allowed/ समय की अनुमति : 45 days (दिन)

The performance guarantee 5% of the tendered amount as FDR A/c No. 606201644000053 dated 11.11.2019 amounting to Rs. 75,100/- (Rupees seventy five thousand one hundred only) valid upto 08.03.2020 issued by Vijaya Bank, 48, Pocket-2, Jasola, New Delhi- 110025 submitted by you, has been considered by the Competent Authority.

सक्षम प्राधिकारी द्वारा विचार किया गया है कि आपके द्वारा प्रस्तुत की गई निविदा राशि की 5% निष्पादन गारंटी के रूप में एफ डी आर खाता संख्या 606201644000053 दिनांक 11.11.2019 रुपये 75,100/- (रुपये पचहत्तर हजार सौ केवल) विजया बैंक, 48, पॉकेट -2, जसोला, नई दिल्ली- 110025 जारी किए गए दिनांक 08.03.2020 तक वैध माना गया है।

You are requested to contact Assistant Engineer- II/SMC for taking possession of the site & start the work.

आपसे अनुरोध है कि साइट पर कब्जा करने और काम शुरू करने के लिए सहायक अभियंता- II/एसएमसी से संपर्क करें।


You are also requested to attend this office along with non-judicial stamp paper worth Rs. 50/- to sign to complete the formal agreement within 7 days from the date of this letter.

आप से यह भी अनुरोध है कि आपको इस कार्यालय में इस पत्र के जारी होने की तारीख से 7 दिनों के भीतर गैर-न्यायिक 50रु/- के स्टैप पेपर के साथ-साथ औपचारिक समझौते पर हस्ताक्षर करने है।

Please note that the time allowed for carrying out the work will be reckoned from the 10th days after the date of issue of this letter to commence the work. Further if you fail to commence the work as specified above, the award letter will be withdrawn by DDA without prejudice to any other right or remedy available on law will be at liberty to forfeit the Earnest Money and performance guarantee absolutely.

कृपया ध्यान दें कि काम करने के लिए अनुमति के समय को 'काम शुरू करने के लिए इस पत्र के जारी होने की तारीख के 10 दिनों के बाद से गिना जाएगा। इसके अलावा यदि आप ऊपर निर्दिष्ट कार्य शुरू करने में असफल हो जाते हैं, तो डीडीए द्वारा किसी भी अन्य अधिकार या कानून पर उपलब्ध उपायों के लिए पूर्वाग्रह से वापस ले लिया जाएगा अग्रिम धन राशि और निष्पादन गारंटी को पूरी तरह से ज़ब्त करने के लिए स्वतंत्र होगा।

Yours faithfully,
आपका विश्वसनीय,


अधिशाषी अभियंता
Executive Engineer,
एसएमसी/डीडीए
SMC/DDA

Copy to (प्रतिलिपि): -

1. Commissioner (Sports)/DDA.
आयुक्त (खेल) / डीडीए

2. Chief Engineer (Sports)DDA
मुख्य अभियंता (खेल) डीडीए
3. Project Director (Sports)/DDA.
परियोजना निदेशक (खेल) / डीडीए
4. Director (System) DDA .
निदेशक (सिस्टम) डीडीए
5. Executive Engineer/QAC-I/DDA
अधिशाषी अभियंता / क्यूएसी- I / डीडीए
6. Dy. CAO/CAU (Sports)/DDA
उप. सीएओ/ सीएयू (खेल) / डीडीए
7. Secy./Coordination.
सचिव।समन्वय
8. Secy/RSC/DDA.
सचिव / आरएससी/ डीडीए
9. Labour Commissioner, Rajpura Road, New Delhi.
श्रम आयुक्त, राजपुरा रोड, नई दिल्ली
10. Dy. Commr. Sales Tax Office Govt. of NCT Room No. 211, Bikri Kar Bhawan, ITO, New Delhi.
उप Commr बिक्री कर कार्यालय सरकार एनसीटी कमरा सं 211, बिक्री कर भवन, आई टी ओ, नई दिल्ली।
11. Trans Yamuna Contractor association (Regd) 11-12 Vir Sawakar Market (Budh Bazar) Gandhi Nagar, New Delhi-110031 (UPC).
यमुना ठेकेदार संघ (रजिग) 11-12 वीर सवाकर बाजार (बुध बाज़ार) गांधी नगर, नई दिल्ली -110031 (यूपीसी)।
12. Delhi Contractors Building association (Regd) No. 5503 Ch. Bhim Singh Road, Delhi (Ch. Prem Raj Bhawan New Chandrawal Road (UPC).
दिल्ली के ठेकेदार बिल्डिंग एसोसिएशन (पंजीकरण) सं। 5503 च।भीम सिंह रोड, दिल्ली (चौ प्रेम राज भवन नई चंद्रावल रोड (यूपीसी)
13. Delhi Contractors Welfare Association (Regd) 306, Masjid Moth, South Extn. Part-II, New Delhi-110049 (UPC).
दिल्ली कन्स्ट्रक्टर्स वेलफेयर एसोसिएशन (रजिड) 306, मस्जिद मॉथ, दक्षिण विस्तार भाग- II, नई दिल्ली - 110049 (यूपीसी)
14. Indian Contractor Association (Regd) G-80/20, Main Bazar Laxmi Nagar, Delhi-110092 (UPC).
भारतीय ठेकेदार एसोसिएशन (रजिड) जी -80 / 20, मुख्य बाजार लक्ष्मी नगर, दिल्ली -110092 (यूपीसी)।
15. Assistant Engineer-II/SMC/DDA for information alongwith copy of schedule of quantities.
जानकारी के लिए सहायक अभियंता- II/एसएमसी/डीडीए, मात्रा के अनुसूची की प्रति के साथ।
16. Head Clerk SMC/ DDA. He is requested to issue the Master Register at once.
हेड क्लर्क एसएमसी/डीडीए उन्हें एक बार में मास्टर रजिस्टर जारी करने का अनुरोध किया जाता है।
17. Accountant SMC/ DDA.
लेखाकार/एसएमसी / डीडीए
18. Copy of agreement.
समझौते की प्रतिलिपि

:4:

- 19. E-mail to ddatender@dda.org.in
ई-मेल को ddatender@dda.org.in
- 20. Guard file
गार्ड फ़ाइल

[Handwritten Signature]
13/1/18

अधिशापी अभियंता
Executive Engineer,
एसएमसी/डीडीए
SMC/DDA

Percentage BoQ

Validate Print Help

Tender Inviting Authority: Executive Engineer/Sports Management Cell

Name of Work: Mio various Sport complexes/Golf Courses. (A/R & M/O works at Rohini Sports Complex for the year of 2019-20)

SH: Providing and laying water proofing treatment over roof and renovation of change room by P/F new G.I. line, sanitary fitting, wall/floor tiles, granite stone flooring and other misc. work at swimming pool Rohini Sports Complex.

Estimated Cost : Rs. 24,21,975/-

NIT No: 15/NIT/AE(P)/EE/SMC/DDA/2019-20

Bidder Name : KEERTIMAN BUILDERS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)


Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Rate	NUMBER # TOTAL AMOUNT	TEXT # TOTAL AMOUNT In Words
1	2 Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	4	5	6	53	55 INR Seventy Six Thousand Five Hundred & Ninety Five and Paise Seventy Five Only
2.00	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. A) For thickness of tiles 10 mm to 25 mm	402.50	Sqm	190.30	76595.75	INR Twenty Eight Thousand Six Hundred & Eighty Six and Paise Fifty Five Only
3.00	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	523.00	Sqm	54.85	28686.55	INR Five Thousand & Thirty One Only
4.00	Dismantling of flushing cistern of all types (C.I./PVC/ vitrous China) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead.	129.00	Sqm	39.00	5031.00	INR Three Thousand Three Hundred & Forty and Paise Seventy Five Only
5.01	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : a) 15 mm to 40 mm nominal bore b) Above 40 mm nominal bore	5.00	each	668.15	3340.75	INR Twenty Eight Thousand Seven Hundred & Sixty Seven and Paise Ninety Only
5.02	Providing and fixing G.I. pipes complete with G.I. fittings and clamps i/c making good the walls etc. concealed pipe, including painting with anti-corrosive bitumastic paint, cutting chases and making good the wall : a) 20 mm dia nominal bore	266.00	Metre	108.15	28767.90	INR Four Thousand & Three and Paise Fifty Only
6.00	Providing and fixing G.I. pipes complete with G.I. fittings and clamps i/c cutting and making good the walls etc. Internal work - Exposed on wall a) 50 mm dia nominal bore	34.00	Metre	117.75	4003.50	INR One Lakh Thirty One Thousand Four Hundred & Thirty and Paise Sixty Only
7.00	Providing and fixing G.I. pipes complete with G.I. fittings and clamps i/c cutting and making good the walls etc. Internal work - Exposed on wall a) 50 mm dia nominal bore	266.00	Metre	494.10	131430.60	INR Twenty Six Thousand Seven Hundred & Forty Nine and Paise Fifty Only
8.00	Providing and fixing unplasticised PVC connection pipe with brass unions : 45 cm length a) 20 mm nominal bore	34.00	Metre	786.75	26749.50	INR Two Thousand Five Hundred & Ten Only
		25.00	each	100.40	2510.00	

9.00	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe a) 32 mm dia	10.00	each	101.10	1011.00	INR One Thousand & Eleven Only
10.00	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 a) 15mm nominal bore	25.00	each	532.00	13300.00	INR Thirteen Thousand Three Hundred Only
11.00	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm sand cast iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required: a) White Vitreous china Orissa pattern W.C. pan of size 680x440 mm with integral type foot rests	5.00	each	5421.50	27107.50	INR Twenty Seven Thousand One Hundred & Seven and Paise Fifty Only
12.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: a) White Vitreous China Flat back wash basin size 550x400 mm with single 15 mm C.P. brass pillar tap	8.00	each	2510.45	20083.60	INR Twenty Thousand & Eighty Three and Paise Sixty Only
13.00	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : a) 150 mm diameter	12.00	each	188.80	2265.60	INR Two Thousand Two Hundred & Sixty Five and Paise Sixty Only
14.00	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : a) One urinal basin with 5 litre white P.V.C. automatic flushing cistern	3.00	each	4982.25	14946.75	INR Fourteen Thousand Nine Hundred & Forty Six and Paise Seventy Five Only
15.00	Providing and fixing rectangular high density polyethylene water storage loft tank with cover, conforming to ISI : 12701, colour of opaque white or as approved by Engineer-in-charge. The rate includes making necessary holes for inlet, outlet & over flow pipes. The base support 1/3 fittings & fixtures for tank shall be paid separately.	8000.00	Per Litre	8.80	70400.00	INR Seventy Thousand Four Hundred Only
16.00	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete	523.00	Sqm	1030.30	538846.90	INR Five Lakh Thirty Eight Thousand Eight Hundred & Forty Six and Paise Ninety Only
17.00	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete.	251.00	Sqm	1088.40	273188.40	INR Two Lakh Seventy Three Thousand One Hundred & Eighty Eight and Paise Forty Only
18.00	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	540.00	Sqm	128.65	69471.00	INR Sixty Nine Thousand Four Hundred & Seventy One Only
19.00	Finishing walls with water proofing cement paint of required shade : a) New work (Two or more coats applied @ 3.84 kg/10 sqm)	313.00	Sqm	91.25	28561.25	INR Twenty Eight Thousand Five Hundred & Sixty One and Paise Twenty Five Only
20.00	Demolishing mud phaska in terracing and disposal of material within 50 metres lead.	33.00	Cum	652.30	21525.90	INR Twenty One Thousand Five Hundred & Twenty Five and Paise Ninety Only

21.00	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roots, balconies, terraces etc consisting of following operations: (a) Applying a slurry coat of neat cement using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over the RCC slab including adjoining walls upto 300 mm height including cleaning the surface before treatment. (b) Laying brick bats with mortar using broken bricks/brick bats 25 mm to 115 mm size with 50% of cement mortar 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge over 20 mm thick layer of cement mortar of mix 1:5 (1 cement : 5 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer-in-charge to required slope and treating similarly the adjoining walls upto 300 mm height including rounding of junctions of walls and slabs. (c) After two days of proper curing applying a second coat of cement slurry using 2.75 kg/sqm of cement admixed with water proofing compound conforming to IS : 2645 and approved by Engineer in-charge. (d) Finishing the surface with 20 mm thick jointless cement mortar of mix 1:4 (1 cement:4 coarse sand) admixed with water proofing compound conforming to IS : 2645 and approved by Engineer in-charge including laying glass fibre cloth of approved quality in top layer of plaster and finally finishing the surface with trowel with neat cement slurry and making pattern of 300x300 mm square 3 mm deep. (e) The whole terrace so finished shall be flooded with water for a minimum period of two weeks for curing and for final test. All above operations to be done in order and as directed and specified by the Engineer-in-Charge :a) With average thickness of 120 mm and minimum thickness at khurra as 65mm	218.00	Sqm	1398.50	304873.00	INR Three Lakh Four Thousand Eight Hundred & Seventy Three Only
22.00	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge. With cement mortar 1:4 (1 cement: 4 coarse sand)	15.00	Sqm	429.60	6444.00	INR Thirteen Thousand & Sixty and Paise Twenty Five Only
23.00	Providing and fixing chromium plated brass curtain rod having wall thickness of 1.25mm with two chromium plated brass brackets fixed with C.P. brass screws and PVC sleeves etc., wherever necessary complete : a) 20 mm dia	35.00	Metre	373.15	13060.25	INR Eight Thousand Nine Hundred & Thirty Two and Paise Fifty Only
24.00	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour. a) 600 mm long towel rail with total length of 645 mm, width 78 mm and effective height of 88 mm, weighing not less than 190gms.	15.00	each	595.50	8932.50	INR Fourteen Thousand Four Hundred & Eighty Two and Paise Eighty Only
25.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. a) Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)	13.50	Cum	1072.80	14482.80	INR Ninety One Thousand Six Hundred & Forty Six and Paise Ten Only
26.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level. a) "1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size).	13.50	Cum	6788.60	91646.10	INR Four Thousand Six Hundred & Two Only
27.01	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :	10.00	each	460.20	4602.00	INR Two Thousand Six Hundred & Seven and Paise Sixty Only
27.02	a) 20 mm nominal bore b) 50 mm nominal bore	3.00	each	869.20	2607.60	INR Two Thousand Six Hundred & Seven and Paise Sixty Only

28.00	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement : 5 coarse sand), including pointing with cement mortar 1:2 (1 cement : 2 stone dust) with an admixture of pigment to match the shade of stone. a) Red sand stone	57.50	Sqrm	1074.55	61786.63	INR Sixty One Thousand Seven Hundred & Eighty Six and Paise Sixty Three Only
29.00	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item). With float glass panes of 4.0 mm thickness (weight not less than 10 kg/ sqm)	83.00	Sqrm	999.60	82966.80	INR Eighty Two Thousand Nine Hundred & Sixty Six and Paise Eighty Only
30.00	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	89.00	Sqrm	121.55	10817.95	INR Ten Thousand Eight Hundred & Seventeen and Paise Ninety Five Only
31.00	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	687.00	Sqrm	18.25	12537.75	INR Twelve Thousand Five Hundred & Thirty Seven and Paise Seventy Five Only
32.00	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	687.00	Sqrm	153.45	105420.15	INR One Lakh Five Thousand Four Hundred & Twenty and Paise Fifteen Only
33.00	Making plinth protection 50mm thick of cement concrete 1:3:6 (1 cement : 3 coarse sand (zone - III) : 6 graded stone aggregate 20 mm nominal size) over 75mm thick bed of dry brick ballast 40 mm nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth.	51.45	Sqrm	614.05	31592.87	INR Thirty One Thousand Five Hundred & Ninety Two and Paise Eighty Seven Only
34.00	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick	77.00	Sqrm	1531.85	117952.45	INR One Lakh Seventeen Thousand Nine Hundred & Fifty Two and Paise Forty Five Only
35.00	Kota stone slabs 20 mm thick in isers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	17.00	Sqrm	1810.05	30770.85	INR Thirty Thousand Seven Hundred & Seventy and Paise Eighty Five Only
36.00	Extra for pre finished nosing in treads of steps of Kota stone/ sand stone slab.	120.00	Metre	148.10	17772.00	INR Seventeen Thousand Seven Hundred & Seventy Two Only
37.00	Dismantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer-in-charge.	247.00	Kg	2.75	679.25	INR Six Hundred & Seventy Nine and Paise Twenty Five Only
38.00	By back of dismantled unserviceable material received from item no. 37 including loading, unloading, lifting all complete from site as per direction of Engineer In Charge	207.00	Kg	20.98	4342.86	INR Minus Four Thousand Three Hundred & Forty Three and Paise Fourteen Only
39.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	247.00	Kg	131.00	32357.00	INR Thirty Two Thousand Three Hundred & Fifty Seven Only
40.00	Providing & fixing PVC cubical shower partition including all fittings , fixtures and locking arrangements all complete in existing shower area of gents & ladies changes rooms of swimming pool as per direction of Engineer in Charge	47.00	Sqrm	1775.40	83443.80	INR Eighty Three Thousand Four Hundred & Forty Three and Paise Eighty Only

41.00	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. (The contractor shall ensure that C&D waste is transported to the C & D Waste site only and due record shall be maintained and submitted to the Engineer-in-charge before payment to the contractor).	27.00	Cum	138.85	3748.95	INR Three Thousand Seven Hundred & Forty Eight and Paise Ninety Five Only
42.00	Add 0% for cost index(Except item No. 38 & 40)	2342874.35	each	0.00	0.00	INR Zero Only
Total in Figures					2421975.29	INR Twenty Four Lakh Twenty One Thousand Nine Hundred & Seventy Five and Paise Twenty Nine Only
Quoted Rate in Figures			Less (-)	37.99%	1501866.88	INR Fifteen Lakh One Thousand Eight Hundred & Sixty Six and Paise Eighty Eight Only
Quoted Rate in Words		INR Fifteen Lakh One Thousand Eight Hundred & Sixty Six and Paise Eighty Eight Only				


 अधिशासक अभियन्ता
 खेल प्रबंधन प्रकोष्ठ
 ०० मेट्रो नई दिल्ली-1100०२
 13/11/2019