



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशाषी अभियंता / O/o Executive Engineer
द्वारका रखरखाव खंड-II / Dwarka Maintenance Division -II
केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka
नई दिल्ली :- ११००७५ / New Delhi -110075
ईमेल - eedmd2@dda.org.in

No.F(54)(2211)/EE/DMD-II/DDA/2026-27/A/1137

Date- 18/9/2026

To

M/s Sanjeev Kumar
606, Village Rangpuri
Mahipalpur, New Delhi - 110037

NIT NO. : 18/EE/DMD-II/DDA/2026-27

N.O.W : M/o various colonies under Nazul A/c-II, Dwarka Zone.
SH : Repair of kerb channel and Painting on Central verge at MP Road no.
201,205,209,210 & 224, Dwarka

Your percentage rate tender for the above noted work has been accepted on behalf of Delhi Development Authority at the rates, terms and conditions given below:-

Estimated cost : Rs. 1,51,07,450 /- (One Crore Fifty One Lakhs Seven Thousand Four Hundred Fifty Rupees Only).

Tendered Amount : Rs. 96,68,768 (Ninety Six Lakh Sixty Eight Thousand Seven Hundred Sixty Eight Only)

Time allowed : 90 Days

Accepted % age : (-) 36 % below the estimated cost

You are requested to attend this office with a non-judicial stamp paper worth Rs. 100/- to sign the formal agreement within **10 (Ten) days** from the date of issue of this letter failing which the acceptance of work in your favor is likely to be withdrawn and entire amount of performance guarantee deposited by you for this work shall be forfeited to the DDA.

You are also requested to contact AE- VI /DMD-II of this division and start the work at once. It may please be noted that the time allowed to carry out the work as entered in the tender document shall be reckoned from **10th day** after the date of issue of letter of acceptance or handing over of site whichever is later to commence the work. You are also requested to obtain the project code within five days from the date of execution of agreement.

EXECUTIVE ENGINEER
DMD-II/DDA

Copy to:

- 1. Chief Engineer (DWK), DDA.**
- 2. Chief Engineer (QAC), Vikas Sadan, DDA**
- 3. S.E./DCC-1, DDA**
- 4. The Income Tax Officer (Contractors' Cell), ITO, New Delhi.**
- 5. Dy. Director (System) DDA with the request to e-mail the same in the website of DDA-ddatender@dda.org.in.**
- 6. Labour Commissioner, 15, Rajpur Road, Delhi.**
- 7. Secretary, CRB, DDA, Vikas Minar, New Delhi.**
- 8. All Ex. Engineers, Dwarka Zone, DDA.**
- 9. A.O(Works)-II, DDA.**
- 10. AO(CAU)/Dwarka, DDA.**
- 11. All AEs, H.C, AAO/DMD-II.**
- 12. AE- VI /DMD-II, DDA, along with Schedule of Quantities & Rates.**
- 13. Agreement copy.**
- 14. Work File.**

Pdha
18.8.26

**EXECUTIVE ENGINEER
DMD-II/DDA**

Validate

Print

Help

Tender Inviting Authority: Delhi Development Authority

Name of work: M/o various colonies under Nazul A/c-II in Dwarka

Sub-head:- Repair of kerb channel and painting on central verge at MP road no 201, 205, 209, 210 & 224, Dwarka.

Contract No: 18/EEDMD-II/DDA/2026-27

Name of the Bidder/ Bidding Firm / Company :

SANJEEV KUMAR

Percentage Boq

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER Rate in Rs. p	NUMBER # TOTAL AMOUNT Rs. p	TEXT # TOTAL AMOUNT In Words
1	1	3	4	5	6	7
1	Cleaning and desilting of kerb channel, bell mouth of any depth and width including taking out dry/wet/semi wet sludge, silt, maba, rubbish etc and disposed off the excavated material for all lead and lift /depth all complete as per direction of Engineer-in-Charge	58912.00	metre	3.25	191464.00	INR One Lakh Ninety One Thousand Four Hundred & Sixty Four Only
2	Providing and laying in position ready mixed or site batched design mix cement concrete for plain cement concrete work, using coarse aggregate and fine aggregate derived from natural sources. Ordinary Portland admixtures in recommended proportions as per IS 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength, including pumping of concrete to site of laying, curing, carriage for all leads, but excluding the cost of centering, shuttering and finishing as per direction of the engineer-in-charge, for the following grades of concrete. Nothing extra shall be paid for using extra cement over minimum specified cement content. Note - Cement content considered in M-20 is @ 270 kg/cum. All works upto plinth level (a) Concrete of M20 grade with minimum cement content of 270 kg /cum less cement used as per design mix is recoverable separately and excess cement will not be paid on this account.	1326.00	cum	9212.60	12215908.00	INR One Crore Twenty Two Lakh Fifteen Thousand Nine Hundred & Eight Only
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) One or more coats on old work.	23093.00	sqm	102.80	2373960.00	INR Twenty Three Lakh Seventy Three Thousand Nine Hundred & Sixty Only
4	Disposal of building rubbish / maba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	545.00	cum	263.95	143853.00	INR One Lakh Forty Three Thousand Eight Hundred & Fifty Three Only
	Amount after GST multiplier @ 973 = 14522205.00					
	Add cost index @ 4.03%				585245.00	INR Five Lakh Eighty Five Thousand Two Hundred & Forty Five Only
Total in Figures					15107450.00	INR One Crore Fifty One Lakh Seven Thousand Four Hundred & Fifty Only

Extra Conditions:

1. The approved design for Agreement Item No. 2, i.e., M20, shall be prepared by the agency, and no payment shall be made to the agency on this account. Hence, agencies are requested to quote amount accordingly.
2. All safety arrangements during execution, such as road barricading, safety cones, traffic diversion, deployment of traffic marshals, etc., shall be the responsibility of the agency, and no payment shall be made to the agency on this account.
3. During execution, if any utilities or services such as sewer lines, water lines, electric cables, sewer wires, etc., are damaged, the agency shall be responsible for rectifying or setting the same at its own cost, and no payment shall be made to the agency on this account.
4. Dewatering/maba from the cleaning of kerb should and residue material from the site will be removed within 24 hours, fail to do so, penalty will be imposed of Rs. 2000 per per lump per day.

Quoted Rate in Figures				
Quoted Rate in Words				
		Less (-)	36.00%	9668768.00 INR Ninety Six Lakh Sixty Eight Thousand Seven Hundred & Sixty Eight Only
INR Ninety Six Lakh Sixty Eight Thousand Seven Hundred & Sixty Eight Only				