



दिल्ली विकास प्राधिकरण  
उप-निदेशक कार्यालय, उद्यान खण्ड - तृतीय  
बी2बी, जनकपुरी, नई दिल्ली-110058



No. F54 (25) DD/Hort.-III/2022-23/DDA/1183

Dated: 18 August, 2022.

To  
M/s Pramod Construction Co.  
A-36, Sarai Extn., Adarsh Nagar  
Delhi-110033.

Name of Work: M/o completed Scheme of N/A-II under SWZ.  
M/o Aff. M.P. Green Area at Hastal Ph.-I.  
Sub Head: S/S of Good earth, Jamuna sand, S/o Plants & Digging of holes, Neem Oil Cake etc. at site.  
PG Ref.: FDR/Bank Guarantee No. 912171 dated 04-08-2022 Amount Rs. 22,364/- from Union Bank, Ashok  
Vihar Branch, New Delhi-52.

Sir,

Your quoted item rates tenders for the above mentioned work has been accepted on behalf of DDA as under:

Estimated cost	:	Rs. 15,20,449.00
Contractor quoted Amount	:	Rs. 7,45,450.00
Accepted tendered Amount	:	Rs. 7,45,450.00 (Rupees Seven Lakhs Forty Five Thousand Four Hundred Fifty Only).
Percentage of tender	:	50.97% below.
Time Allowed	:	45 Days.

The item to be taken for the purpose of clause-12 shall be 50.97% below on rates based on DSR-2020/Market Rates. You are requested to attend the office to sign the agreement along with non-judicial stamp paper worth Rs. 100/- within ten (10) days from the date of issue of this letter, failing, which the acceptance of tender is likely to be withdrawn and the earnest money forfeited. You are therefore, directed to contact the AD-III of this office and start the work at once. Please note that the time allowed for carrying out the work as entered in the tender still be reckoned after the ten days from the date of issue of this letter to commence the work. Your letter dated 06.08.2022 shall be part of the Agreement.

Copy to:

1. Director (Hort.) NW, DDA.
2. Dy. Director (QC) III, DDA.
3. A.O. (W) II, DDA.
4. A.O. (CAU) Dwarka, DDA.
5. Dy. Dir. Hort. II, V, VIII & Dwarka, DDA.
6. Income Tax Commr. W No. \_\_\_\_\_ New. Delhi.
7. A.D.-I, Hort. Div. - III, DDA.
8. Comm. Sale Tax. NCT Delhi.
9. File Concern.
10. Agreement File.
11. DDA website <https://eprocure.gov.in/eprocure/app> or [www.dda.org.in](http://www.dda.org.in) or [cxxx-nic@nic.in](mailto:cxxx-nic@nic.in)

Dy. Director (Hort.) - III/DDA

Dy. Director (Hort.) - III/DDA

Validate

Print

Help

## Item Rate BoQ

Tender Inviting Authority: DELHI DEVELOPMENT AUTHORITY DY. DIRECTOR (HORT.) III

Name of Work: Name of Work: M/o Complete scheme of N/A- II under SWZ.

M/o Aff. M.P. Green Area at Hastal Ph.- I

Sub Head: S/S of Good earth, Jamuna sand, S/o Plants &amp; digging of holes, Neem oil cake etc. at site.

Contract No: 011-25507273, NIT No. 25/DD/Hort.-III/DDA/2022-23 E.C Rs. 15,20,449/-

Name of the Bidder/ Bidding Firm / Company :	M/S PRAMOD CONSTRUCTION CO.
--	-----------------------------

## PRICE SCHEDULE


(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder In Rs. P	TOTAL AMOUNT Without Taxes In Rs. P
1	2	4	5	13	53
1	Supply and stacking of good earth at site by including mechanical transport royalty and carriage, loading unloading with all lead and lift. ( Good Earth measured in stacks will be reduced for 20% payment )	308.00	Cum	350.00	107800.00
2	Supply and stacking of Jamuna Sand at site by mechanical transport including royalty carriage and loading unloading for all lead and lift.	108.00	Cum	800.00	86400.00
3	Supply and Stacking of Red Bajri at site including royalty and carriage by mechanical transport and loading unloading with all lead and lifts.	18.00	Cum	1000.00	18000.00
4	Earth work in excavation by mechanical means (Hydraulic Excavator)/manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead up to 50 m and lift up to 1.5 m, as per direction of engineer-in-charge. 5m x 4m x 1.5m x 3 Nos.= 90 cum. (Manure Pit).	90.00	Cum	150.00	13500.00
5	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately):				
5.1	Holes 90 cm dia., and 90 cm deep	100.00	Each	70.00	7000.00
5.2	Holes 60 cm dia., and 60 cm deep	800.00	Each	25.00	20000.00
6	Supply of Tree Plants:				
6.1	Providing and stacking of Pongamia glabra (Papri) of height 120-135 cm. in big poly bag of size 25 cm as per direction of the officer-in-charge.	150.00	Each	25.00	3750.00
7	Supply of Hedge Plant:				
7.1	Providing and stacking of Clerodendrum inerme of ht. 20 cm to 30 cm multi branched in 15 cm size of Earthen Pot/Plastic Pot & as per direction of the officer-in-charge.	6500.00	Each	5.00	32500.00
8	Supply of Shrub Plant:				
8.1	Providing and stacking of Hibiscus rosasinensis of height 90-105 cm., bushy in big size HDPE bag as per direction of the officer-in-charge.	600.00	Each	20.00	12000.00



8.2	Providing and Stacking of Karonda of ht. 45-60cm in Poly bag of size 25 cm. as per direction of the officer-in-charge.	400.00	Each	13.00	5200.00
9	<b>Supply of Foliage and Shade Loving Plants:</b>				
9.1	Providing and stacking of Syngonium Variegated plant, mounted on moss stick 90 cm ht., 3 to 4 plants placed in each pot at equal distance, well developed with full of fresh & healthy leaves from bottom to top in 25 cm size of Earthen pot / Plastic pot & as per direction of the officer-in-charge.	500.00	Each	20.00	10000.00
9.2	Providing and stacking of Raphis palm plant, having ht. 45 cm to 60 cm with 5 to 7 suckers, well developed, full of fresh and healthy leaves in 25 cm size of Earthen pot / Plastic pot & as per direction of the officer-in-charge.	500.00	Each	60.00	30000.00
9.3	Providing and stacking of Dracaena Song of India plant (three in one), having ht. 30 cm and above, multibranched, well developed with fresh and healthy leaves in 25 cm size of Earthen pot / Plastic pot & as per direction of the officer-in-charge.	500.00	Each	25.00	12500.00
9.4	Providing and stacking of Areca Palm plant, having ht. 90 cm to 1.20 m with 4 to 5 suckers, well developed, fresh and healthy with lush green foliage in 20 cm size of Earthen pot / Plastic pot & as per direction of the officer-in-charge.	500.00	Each	80.00	40000.00
9.5	Providing and displaying of Croton Baby Golden Punctatum Aureum having ht. 23 cm to 30 cm, well developed with fresh and healthy foliage in 15 cm size of Earthen pot/Plastic pot. as per direction of the officer-in-charge.	500.00	Each	30.00	15000.00
9.6	Providing and stacking of Diffenbachia Tropic-snow plant, having ht. 60cm & above with 8 - 10 leaves, well developed, fresh & healthy in 25 cm size of Earthen pot / Plastic pot & as per direction of the officer-in-charge.	200.00	Each	80.00	16000.00
9.7	Providing and stacking of Bougainvillea (Variety Butiana, Lady Mary Baring, Mahara, Mohan, Scarlet Queen, Variegated, Glabra Formosa, Peruviana Odissi, Paratha, Subhra, Thimma, Spectabilis L.N Birla, Refulgens) of height 30 cm. to 45 cm. with 2-3 branches in 20 cm size of Earthen pots / Plastic pots & as per direction of the officer-in-charge.	300.00	Each	20.00	6000.00
10	Hiring of J.C.B/Hydraulic excavator (3-D) with driver, fuel and helper etc. for cleaning of wild growth, removal of building rubbish, debris industrial waste and refuse etc. as per direction of Engineer-in-charge.	10.00	Day	6500.00	65000.00
11	Supply of Polythene bags size 6" x 8" (gauge 175-200) both layer at site. (only for seed bed/nursery).	500.00	KG	120.00	60000.00
12	Supply of Neem oil cake in 40 kg packing bag at site.	23.00	Bag	500.00	11500.00
13	Supply of best quality Agro shade net green colour (50X3m) 75:25 ratio.	500.00	Sqm	20.00	10000.00
14	<b>Provision of empty earthen pots for seed bed/nursery:</b>				
14.1	Supply of empty earthen pots. Top inside dia 20 cm, outer bottom dia 12 cm, 20 cm perpendicular height size 8" (Special).	1500.00	Each	10.00	15000.00
14.2	Supply of empty earthen pots. Top inside dia 25 cm, outer bottom dia 15 cm, 25 cm perpendicular height size 10" (Special).	1500.00	Each	12.00	18000.00
14.3	Supply of empty earthen pots. Top inside dia 30 cm, outer bottom dia 20 cm, 30 cm perpendicular height size 12" (Special).	500.00	Each	15.00	7500.00
15	Supply of Chlorpyrifos 20% E.C./Lindane 20% E.C. (Insecticide/pesticide)	8.00	Litre	150.00	1200.00
16	Provision of Leaf Mulcher Machine with Power 7.5 HP 3phase Specification; electric motor with motor starter, 4 mm heavy duty body, heavy duty caster wheel, carbon steel 48 blades with pulley and drive system	1.00	Each	85000.00	85000.00

17	Supply of galvanised steel barbed wire.	5.00	Qtl.	4300.00	21500.00
18	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludges or manure in the ratio of 8:1( 8 parts of stacked volume of earth after reduction by 20%: one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary , watering and finally fine dressing, levelling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and levelling as directed, within a lead of 50 m , lift up to 1.5 m complete ( cost of sludge, manure or extra earth to be paid for separately).	90.00	Cum	150.00	13500.00
19	Supply of Moss Stick ht. 3 feet at site.	20.00	Each	20.00	400.00
20	Supply of Moss Grass at site.	20.00	Per KG	60.00	1200.00
Total in Figures					745450.00
Quoted Rate in Words		INR Seven Lakh Forty Five Thousand Four Hundred & Fifty Only			

  
 उप-निदेशक (उद्यान)  
 उद्यान-खण्ड-3,  
 दिल्ली विकास प्राधिकरण।