



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092 (E-mail: eehcdx@gmail.com)

No. F.1 (31)2022-23/A/c/HCD-10/DDA/ 390

Dated: 28/4/23

To,

M/s Savita Construction Company
C-9/399 A, Brijpuri Delhi
Delhi -110094
M. No. 8178247581, 9868467905

Name of work: Land Protection work in TYA Nazul A/c-II (East zone).
Sub Head: Raising & Repair of existing boundary wall, gates etc. at
Yamuna Bio-Diversity Park Phase -I
NIT No.: 12/EE/HCD-10/DDA/2022-23
Estimated cost: Rs. 5660912/-

Dear Sir(s),


Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:

1.	Estimated Cost	Rs.5660912/- (Rupees Fifty Six Lakh Sixty Thousand Nine Hundred Twelve only).
2.	Quoted & Accepted Rate	(-)42.60% (Forty Two point six zero percent) below on the Estimated Cost.
3.	Quoted Tender Amount	Rs. 32,49,363.49 (Rupees Thirty Two Lakh Forty Nine Thousand Three Hundred Sixty Three and paise Forty Nine only).
4.	Accepted Tender Amount	Rs. 32,49,363.49 (Rupees Thirty Two Lakh Forty Nine Thousand Three Hundred Sixty Three and paise Forty Nine only).

Time allowed for carrying out the work shall **180 (One hundred eighty) days** only. You are requested to contact A.E.-VI/HCD-10/DDA of this division and start the work immediately.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from **10th day** after the date of issue of this letter to commence the work.


28-4-23
Executive Engineer
HCD-10/D.D.A.

Copy to:-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi - 110023.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi-110002.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE-VI/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. Agreement copy.

AV
28.4.23
Executive Engineer
HCD-10/D.D.A.

Validate

Print

Help

Percentage BoQ

Tender Inviting Authority: EXECUTIVE ENGINEER

Name of Work: Land Protection work in TYA Nazul A/c-II (East zone).

Sh:- Raising & Repair of existing boundary wall, gates etc. at Yamuna Bio-Diversity Park Phase-I.

NIT No: 12/EE/HCD-10/DDA/2022-23

Name of the Bidder/
Bidding SAVITA CONSTRUCTION CO.

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	
1	2 Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	3	4 Cum	5 286.85	6 31554	7 INR Thirty One Thousand Five Hundred & Fifty Four Only	
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 fine sand derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	4.00	Cum	5660.45	22642	INR Twenty Two Thousand Six Hundred & Forty Two Only	
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources) : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	52.14	Cum	7365.15	384019	INR Three Lakh Eighty Four Thousand & Nineteen Only	
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in Cement mortar 1:6 (1 cement : 6 coarse sand)	9.00	Cum	6658.25	59924	INR Fifty Nine Thousand Nine Hundred & Twenty Four Only	

5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand)	42.00	Cum	8288.35	348111	INR Three Lakh Forty Eight Thousand One Hundred & Eleven Only
6	Providing and laying autoclaved aerated cement blocks masonry with 100 mm thick AAC blocks in super structure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand). The rate includes providing and placing in position 2 Nos 6 mm dia M.S. bars at every third course of masonry work	225.00	Cum	8890.80	2000430	INR Twenty Lakh Four Hundred & Thirty Only
7	Random rubble masonry with hard stone in foundation and plinth including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	82.00	Cum	6653.45	545583	INR Five Lakh Forty Five Thousand Five Hundred & Eighty Three Only
8	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like Cement mortar 1:6 (1 cement : 6 coarse sand)	21.00	Cum	8275.70	173790	INR One Lakh Seventy Three Thousand Seven Hundred & Ninety Only
9	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1752.00	Kg	93.05	163024	INR One Lakh Sixty Three Thousand & Twenty Four Only
10	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	300.00	Kg	111.95	33585	INR Thirty Three Thousand Five Hundred & Eighty Five Only
11	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) Raised and cut pointing	2740.00	Sqm	580.25	1589885	INR Fifteen Lakh Eighty Nine Thousand Eight Hundred & Eighty Five Only
12	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick	3.00	Sqm	1706.60	5120	INR Five Thousand One Hundred & Twenty Only
13	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old work	73.00	Sqm	86.55	6318	INR Six Thousand Three Hundred & Eighteen Only
14	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	19.00	Cum	1698.45	32271	INR Thirty Two Thousand Two Hundred & Seventy One Only

15	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	15.00	Cum	2027.10	30407	INR Thirty Thousand Four Hundred & Seven Only
16	Providing and fixing concertina coil fencing with punched tape concertina nos rounds per 6 metre length (total length 90 m), having 50 iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	660.00	Metre	303.65	200409	INR Two Lakh Four Hundred & Nine Only
17	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	120.00	Sqm	282.00	33840	INR Thirty Three Thousand Eight Hundred & Forty Only
Total In Figures					5660912.00	INR Fifty Six Lakh Sixty Thousand Nine Hundred & Twelve Only
Quoted Rate in Figures					3249363.49	INR Thirty Two Lakh Forty Nine Thousand Three Hundred & Sixty Three and Paise Only
Quoted Rate in Words			Less (-)	42.60%		INR Thirty Two Lakh Forty Nine Thousand Three Hundred & Sixty Three and Paise Only
						INR Thirty Two Lakh Forty Nine Thousand Three Hundred & Sixty Three and Paise Forty Nine Only


Executive Engineer
HCD-10/DDA