



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092
E-mail: eehcdx@gmail.com

No. F.1 (04)2026-2027/EE/HCD-10/A/DDA/ 173

Date: 31-8-26

To,

M/s N.K. Constructions
D-368, Ganesh Nagar
Padav Nagar Complex
Delhi - 110092
M. No. 9911656527
e-mail : nkconstruction99@gmail.com

Name of work : M/o Completed Scheme under NA-II (Hort. Zone).
SH : Annual maintenance work of Yamuna Bio-Diversity Park Phase-I.
E-tender ID : 2026_DDA_910005_1
NIT No. : 03/EE/HCD-10/DDA/2026-2027 (03/EE(P)/HCC-3/DDA/2026-27)
Estimated cost: Rs. 80,39,881/-
Earnest money: Rs. 1,60,798/-
Time Allowed: 365 Days
Ref : P.G. submitted in shape of FDR A/c No 45500833836 dated 24/08/2026 amounting to Rs 4,71,137/-

Dear Sir(s),

Your percentage rate tender for the above-mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rate subject to following terms & condition: -

1.	Estimated Cost	Rs. 80,39,881/- (Rupees Eighty Lakh Thirty Nine Thousand Eight Hundred Eighty One Only).
2.	Quoted and Accepted Amount	@ (-) 20.86% (Twenty point Eight Six Percent) below on estimated cost.
3.	Quoted tender amount	Rs. 63,62,761.82/- (Rupees Sixty Three Lakh Sixty Two Thousand Seven Hundred Sixty One and Paise Eighty Two Only)
4.	Accepted Tender Amount	Rs. 63,62,761.82/- (Rupees Sixty Three Lakh Sixty Two Thousand Seven Hundred Sixty One and Paise Eighty Two Only)


Time allowed for carrying out the work shall 365 Days only.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after the date of issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work. You are requested to contact A.E-V/HCD-10/DDA of this division and start the work immediately.

Thanking you,

Yours faithfully


(Sandeep Kushwaha)
Executive Engineer
HCD-10/D.D.A.

Print

Help

Percentage BoQ

Tender Inviting Authority: Delhi Development Authority

Name of Work: M/o completed scheme under NA-II Hort. Zone.

SH:- Annual maintenance work of Yamuna Bio-Diversity Park Phase-I.

NIT No: 03/EE(P)/HCC-3/DDA/2026-27

03/EE/HCD-10/DDA/2026-27

Name of
the Bidder/
Bidding
Firm /

N K CONSTRUCTIONS

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender.
Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	90.00	cum	177.50	15975	INR Fifteen Thousand Nine Hundred & Seventy Five Only
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift.	25.00	cum	196.00	4900	INR Four Thousand Nine Hundred Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (a) 1:5:10 (1 cement : 5 coarse sand (zone-III): 10 graded stone aggregate 40 mm nominal size).	46.00	cum	6518.60	299856	INR Two Lakh Ninety Nine Thousand Eight Hundred & Fifty Six Only
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	6.00	cum	7878.50	47271	INR Forty Seven Thousand Two Hundred & Seventy One Only
5	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	45.00	sqm	392.15	17647	INR Seventeen Thousand Six Hundred & Forty Seven Only
6	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts	10.00	sqm	961.30	9613	INR Nine Thousand Six Hundred & Thirteen Only

7	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)	15.00	cum	1503.60	22554	INR Twenty Two Thousand Five Hundred & Fifty Four Only
8	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge : In cement mortar	15.00	cum	2458.95	36884	INR Thirty Six Thousand Eight Hundred & Eighty Four Only
9	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge In cement mortar	3.00	cum	2060.20	6181	INR Six Thousand One Hundred & Eighty One Only
10	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	20.00	cum	7370.65	147413	INR One Lakh Forty Seven Thousand Four Hundred & Thirteen Only
11	Brick work with clay flyash F.P.S. (non modular) brick of class designation 7.5 in superstructure above plinth level up to floor five level in : Cement mortar 1:6 (1 cement : 6 coarse sand)	13.00	cum	9095.05	118236	INR One Lakh Eighteen Thousand Two Hundred & Thirty Six Only
12	Washed stone grit plaster on exterior walls height upto 10 metre above ground level, in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 Kg of cement per square metre, top layer 15 mm cement plaster 1:1/ 2:2 (1 cement: 1/2 coarse sand : 2 stone chipping 10 mm nominal size), in panels with groove all around as per approved pattern, including scrubbing and washing the top layer with brushes and water to expose the stone chippings ,complete as per specification and direction of Engineer-in-charge (payment for providing grooves shall be made separately).	110.00	sqm	1162.25	127848	INR One Lakh Twenty Seven Thousand Eight Hundred & Forty Eight Only
13	12 mm cement plaster of mix : 1:6 (1 cement: 6 coarse sand)	150.00	sqm	333.35	50003	INR Fifty Thousand & Three Only
14	12 mm cement plaster of mix : 1:4 (1 cement: 4 coarse sand)	150.00	sqm	357.35	53603	INR Fifty Three Thousand Six Hundred & Three Only
15	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand)(Stone will be provided by department)	23.00	cum	7496.95	172430	INR One Lakh Seventy Two Thousand Four Hundred & Thirty Only
16	Random rubble masonry with hard stone in superstructure above plinth level and upto floor five level, including leveling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) at window sills, ceiling level and the like. Cement mortar 1:6 (1 cement : 6 coarse sand)	54.00	cum	9275.45	500874	INR Five Lakh Eight Hundred & Seventy Four Only

17	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement: 6 coarse sand) (Stone will be provided by department)	16.00	cum	5035.00	80560	INR Eighty Thousand Five Hundred & Sixty Only
18	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with Cement mortar 1:6 (1 cement : 6 coarse sand)	38.00	cum	7311.25	277828	INR Two Lakh Seventy Seven Thousand Eight Hundred & Twenty Eight Only
19	Providing and laying autoclaved aerated cement blocks masonry with 100 mm thick AAC blocks in super structure above plinth level up to floor V level in cement mortar 1:4 (1 cement : 4 coarse sand). The rate includes providing and placing in position 2 Nos 6 mm dia M.S. bars at every third course of masonry work.	22.00	cum	10195.45	224300	INR Two Lakh Twenty Four Thousand Three Hundred Only
20	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) (a) Raised and cut pointing	200.00	sqm	701.05	140210	INR One Lakh Forty Thousand Two Hundred & Ten Only
21	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	4.00	cum	9895.20	39581	INR Thirty Nine Thousand Five Hundred & Eighty One Only
22	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work sqm	100.00	sqm	102.80	10280	INR Ten Thousand Two Hundred & Eighty Only
23	Providing and laying Polished Granite stone flooring in required design and patterns, inlinear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in Charge. Polished Granite stone slab of colour Black, Cherry/Ruby	20.00	sqm	4481.30	89626	INR Eighty Nine Thousand Six Hundred & Twenty Six Only
24	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	100.00	sqm	54.65	5465	INR Five Thousand Four Hundred & Sixty Five Only
25	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	70.00	sqm	73.40	5138	INR Five Thousand One Hundred & Thirty Eight Only

26	Providing and laying matt finished vitrified tile of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	20.00	sqm	1455.65	29113	INR Twenty Nine Thousand One Hundred & Thirteen Only
27	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 500x500 mm	30.00	sqm	1524.30	45729	INR Forty Five Thousand Seven Hundred & Twenty Nine Only
28	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc (a) 20 mm nominal dia Pipes	50.00	metre	537.60	26880	INR Twenty Six Thousand Eight Hundred & Eighty Only
29	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. (FINOLEX/SUPREME/PRINCE) External work (a) 50 mm nominal dia Pipes	10.00	metre	794.25	7943	INR Seven Thousand Nine Hundred & Forty Three Only
30	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1: 4 (1 cement : 4 coarse sand) : 25 mm thick	40.00	sqm	1948.25	77930	INR Seventy Seven Thousand Nine Hundred & Thirty Only
31	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	20.00	sqm	2354.70	47094	INR Forty Seven Thousand & Ninety Four Only
32	Painting on G.S. sheet with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : Old work (one or more coats)	100.00	sqm	93.30	9330	INR Nine Thousand Three Hundred & Thirty Only
33	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	200.00	sqm	156.05	31210	INR Thirty One Thousand Two Hundred & Ten Only

Providing and
decorative ty
and well ma
veneers on
butt hinges

	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	10.00	sqm	3167.95	31680	INR Thirty One Thousand Six Hundred & Eighty Only
35	Providing and fixing to existing door frames. 24 mm thick factory made PVC door shutters made of styles and rails of a uPVC hollow section of size 59x24 mm and wall thickness 2 mm (± 0.2 mm) with inbuilt edging on both sides. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 20x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x24 mm and 2 mm (± 0.2 mm) wall thickness, fixed to the shutter styles by means of plastic/galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi-chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness. The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge. (For W.C. and bathroom door shutter).	2.50	sqm	2969.25	7423	INR Seven Thousand Four Hundred & Twenty Three Only
36	Engagement of environment assistant (unskilled category) for the removal of hyacinth/garbage/rubbish etc from oxidation ponds/wetland/under-mud etc. including stacking the same outside the periphery of pond/wetland, all complete as per site requirement & direction of Engineer-in-charge.	285.00	Per Job Per Day	1026.20	292467	INR Two Lakh Ninety Two Thousand Four Hundred & Sixty Seven Only
37	Hiring and deployment of Hydraulic Excavator (3D) with driver and fuel all complete as per direction of Engineer-in-charge.	45.00	Day	11167.70	502547	INR Five Lakh Two Thousand Five Hundred & Forty Seven Only
38	Hiring and deployment of Tractor with trolley with driver and fuel all complete as per direction of Engineer-in-charge.	90.00	Day	1920.55	172850	INR One Lakh Seventy Two Thousand Eight Hundred & Fifty Only
39	Earth work by mechanical / manual means in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods, watering, rolling each layer with "2 tonne roller or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead upto 50 m and for all lift :All kinds of soil	90.00	cum	395.30	35577	INR Thirty Five Thousand Five Hundred & Seventy Seven Only
40	Supplying and stacking at site.Moorum	25.00	Cum	768.25	19206	INR Nineteen Thousand Two Hundred & Six Only
41	Supplying and stacking at site.Good earth	50.00	cum	775.50	38775	INR Thirty Eight Thousand Seven Hundred & Seventy Five Only
42	Supplying, stacking and Spreading 6 mm thick red bajri, watering and rolling complete including preparation of the surface and rolling. (a) With road roller/ hand roller	1000.00	sqm	24.45	24450	INR Twenty Four Thousand Four Hundred & Fifty Only

43	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	550.00	metre	39.35	21643	INR Twenty One Thousand Six Hundred & Forty Three Only
44	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	110.00	metre	109.45	12040	INR Twelve Thousand & Forty Only
45	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement: 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5 mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured to calculate volume for payment). (Precast C.C. kerb stone shall be approved by Engineer-in-charge).	20.00	cum	10117.60	202352	INR Two Lakh Two Thousand Three Hundred & Fifty Two Only
46	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	700.00	sqm	131.75	92225	INR Ninety Two Thousand Two Hundred & Twenty Five Only
47	Laying old cement concrete interlocking paver blocks of any design/ shape laid in required line, level, curvature, colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge. (Old CC paver blocks shall be supplied by the department free of cost).	140.00	sqm	402.95	56413	INR Fifty Six Thousand Four Hundred & Thirteen Only
48	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50 mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	560.00	sqm	972.00	544320	INR Five Lakh Forty Four Thousand Three Hundred & Twenty Only
49	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be struted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire	1500.00	meter	22.10	33150	INR Thirty Three Thousand One Hundred & Fifty Only

50	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	500.00	kg	5.65	2825	INR Two Thousand Eight Hundred & Twenty Five Only
51	(-) deduct for disposal of various iron scrap, as and where basis; as per direction of engineer-in-charge	500.00	kg	-30.00	-15000	INR Minus Fifteen Thousand Only
52	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2500.00	kg	133.70	334250	INR Three Lakh Thirty Four Thousand Two Hundred & Fifty Only
53	steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes	1500.00	kg	194.40	291600	INR Two Lakh Ninety One Thousand Six Hundred Only
54	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.)	500.00	kg	772.40	386200	INR Three Lakh Eighty Six Thousand Two Hundred Only
55	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 25 mm nominal dia Pipes	585.00	metre	355.40	207909	INR Two Lakh Seven Thousand Nine Hundred & Nine Only
56	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 65 mm nominal dia Pipes	765.00	metre	1674.40	1280916	INR Twelve Lakh Eighty Thousand Nine Hundred & Sixteen Only
57	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete : 15 mm nominal bore	35.00	no's	406.85	14240	INR Fourteen Thousand Two Hundred & Forty Only

58	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	250.00	kg	495.05	123763	INR One Lakh Twenty Three Thousand Seven Hundred & Sixty Three Only
59	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer-in-charge. 21.2.1 Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side	20.00	sqm	1139.30	22786	INR Twenty Two Thousand Seven Hundred & Eighty Six Only
60	Providing and Fixing Scaffolding net made of high density polyethylene UV stabilized having density 100 gm/sqm green garden net all complete as per the direction of Engineer-in-charge.	500.00	sqm	155.05	77525	INR Seventy Seven Thousand Five Hundred & Twenty Five Only
61	Providing and Fixing polycarbonet roofing sheet 3mm all complete as per the direction of Engineer-in-charge.	200.00	sqm	124.55	24910	INR Twenty Four Thousand Nine Hundred & Ten Only
62	Providing and fixing Bamboo jaffery/ fencing consisting of superior quality 25 mm dia (Average) half cut bamboo placed vertically and fixed together with three numbers horizontal running members of hollock wood in scantling of section 50X25 mm, fixed with nails and G.I wire on existing support complete as per direction of Engineer-in-charge.	25.00	sqm	689.40	17235	INR Seventeen Thousand Two Hundred & Thirty Five Only
63	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	90.00	cum	263.95	23756	INR Twenty Three Thousand Seven Hundred & Fifty Six Only
64	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge. Made of G.I. wire of dia 4 mm	150.00	sqm	1017.80	152670	INR One Lakh Fifty Two Thousand Six Hundred & Seventy Only

excavating tre
cables, etc in
bottoms, for a
soil as require
deposited lay
directed, withi

	Excavating trenches by mechanical / manual means of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, for all depth, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : Pipes, cables etc, not exceeding 80 mm dia	1300.00	metre	215.60	280280	INR Two Lakh Eighty Thousand Two Hundred & Eighty Only
66	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying pressure conforming to class II of ASTM-D-4956-01 and fixing the same to the plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge. (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). Overhead informatory road signage	20.00	sqm	5879.90	117598	INR One Lakh Seventeen Thousand Five Hundred & Ninety Eight Only
67	Construction of granular sub-base by providing close graded Material conforming to specifications, mixing in a mechanical mix plant at OMC, carriage of mixed material by tippers to work site, for all leads & lifts, spreading in uniform layers of specified thickness with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge. With material conforming to Grade-I (size range 75 mm to 0.075 mm) having CBR Value-30	19.00	cum	2784.00	52896	INR Fifty Two Thousand Eight Hundred & Ninety Six Only
	Correction factor (0.973)					
Total in Figures					8039881.00	INR Eighty Lakh Thirty Nine Thousand Eight Hundred & Eighty One Only
Quoted Rate in Figures			Less (-)	20.86%	6362761.82	INR Sixty Three Lakh Sixty Two Thousand Seven Hundred & Sixty One and Paise Eighty Two Only
Quoted Rate in Words			INR Sixty Three Lakh Sixty Two Thousand Seven Hundred & Sixty One and Paise Eighty Two Only			


 Executive Engineer
 HCD-40/DDA