



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092 (E-mail: eehcdx@gmail.com)

No. F.1 (35)2023-2024/A/cs/HCD-10/DDA/ 661

Dated:- 23/6/23

To,

M/s A.K. Builders

G-241, Sector-56,

Noida-201301

Mobile : 9810590018

E-mail: akbuilders28@yahoo.co.in

Name of work: Land Protection work in TYA Nazul A/c-II (East Zone).
Sub Head: Providing and Fixing Security Guard Cabin and RBT Fencing with
RCC post at Plantation Site in the area between Wazirabad Barrage
to Old Iron Bridge (Eastern Bank).
NIT No. : 01/EE/HCD-10/DDA/2023-2024
01/EE(P)/SE/HCC-3/DDA/ 2023-24
Estimated cost: Rs. 22861947/-

Dear Sir(s),

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:-


1.	Estimated Cost	Rs. 22861947/- (Rupees Two Crore Twenty Eight Lakh Sixty One Thousand Nine Hundred Forty Seven only).
2.	Quoted & Accepted Rate	(-) <u>36.73%</u> (Thirty Six point seven three percent) below on the Estimated Cost.
3.	Quoted Tender Amount	Rs.14464753.87 (Rupees One Crore Forty Four Lakh Sixty Four Thousand Seven Hundred Fifty Three and Paise Eighty Seven only).
4.	Accepted Tender Amount	Rs.14464753.87 (Rupees One Crore Forty Four Lakh Sixty Four Thousand Seven Hundred Fifty Three and Paise Eighty Seven only).

Time allowed for carrying out the work shall **90 Days** only. You are requested to ~~contact~~ *contact* ~~N.E.A~~ / HCD-10 / DDA of this division and start the work immediately.

You are requested to attend this office for drawing formal agreement along with a ~~non-judicial~~ stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after issue of this letter, failing which the acceptance of the work is likely to be withdrawn.


Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work.

Thanking you,

Yours Faithfully

(Bhupendra Kumar)
Executive Engineer
HCD-10/D.D.A.

Copy to:-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi - 110023.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi-110002.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE-I/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. Agreement copy.


Executive Engineer
HCD-10/D.D.A.

Percentage BoQ

Tender Inviting Authority: Delhi Development Authority

Name of Work: Land Protection work in TYA Nazul A/c-II (East zone)

SH:- Providing and Fixing Security Guard Cabin and RBT Fencing with RCC post at plantation site in the area between Wazirabad Barrage to Old iron Bridge (Eastern Bank).

NIT No: 01/EE/HCD-10/DDA/2023-2024
01/EE(P)/SE/HCC-3/DDA/2023-24

Name of the Bidder/ Bidding Firm / A.K BUILDERS

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sl. No.	Item Description	NUMBER #	Quantity	TEXT #	Units	NUMBER	Estimated Rate in Rs. P	NUMBER #	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words	TEXT #
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	2	3	4	cum	5	218.60	6	5246.40	INR Five Thousand Two Hundred & Forty Six Only	7
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and for all lift.		23.00		cum		161.60		3716.80	INR Three Thousand Seven Hundred & Seventeen Only	
3	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc. disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m. All kinds of soil		2397.00		each		69.40		166351.80	INR One Lakh Sixty Six Thousand Three Hundred & Fifty Two Only	
4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)		20.00		cum		6658.25		133165.00	INR One Lakh Thirty Three Thousand One Hundred & Sixty Five Only	

5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 fine sand derived from natural sources) : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	10.50	cum	5660.45	59434.73	INR Fifty Nine Thousand Four Hundred & Thirty Five Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources) : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	6.25	cum	7365.15	46032.19	INR Forty Six Thousand & Thirty Two Only
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size)	669.00	cum	6833.40	4571544.60	INR Forty Five Lakh Seventy One Thousand Five Hundred & Forty Five Only
8	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), Jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	80.00	sqm	935.60	74848.00	INR Seventy Four Thousand Eight Hundred & Forty Eight Only
9	12 mm cement plaster of mix : 1:6 (1 cement: 6 fine sand)	36.00	sqm	282.00	10152.00	INR Ten Thousand One Hundred & Fifty Two Only
10	Supplying at site : R.C.C. post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar ribs wherever required as per direction of Engineer-in-charge (cost of earth works in excavation, concrete works in foundation to be paid separately).	480.00	Cum	29105.40	13970592.00	INR One Crore Thirty Nine Lakh Seventy Thousand Five Hundred & Ninety Two Only
11	Fencing with RCC Posts placed at required distance, embedded in Cement Concrete block every 15th post, last but one end post and corner post shall be struted on both side and end posts one side only. Provided with horizontal line and two diagonals of Reinforced Barbed Tape (RBT) of high tensile strength of 165 kg/sqmm.. with tape 0.52 mm thick and weight 43.478 gm. per meter between the two posts fitted and fixed with G.I. Staples on wooden plugs or G.I. binding wire tied to 6mm bar ribs fixed while casting the posts (costs of RCC Posts, Struts, Earth Work and Concrete to be paid separately) : Payment to be made per meter cost of total length of reinforce barbed tape (RBT) used.	149785.00	Mtr.	15.80	2366603.00	INR Twenty Three Lakh Sixty Six Thousand Six Hundred & Three Only

12	Providing & fixing pre fabricated portable security cabin at site in FRP (Fiberglass Reinforced plastic) of size 6' X 6' including necessary fittings, fixtures whether proof all complete as per direction of Engineer-in-charge.	5.00	each	49792.00	248960.00	INR Two Lakh Forty Eight Thousand Nine Hundred & Sixty Only	
	Add GST factor @0.0633 at DSR item Sl.no. 1 to 10				1205300.59	INR Twelve Lakh Five Thousand Three Hundred & One Only	
Total in Figures					22861947.00	INR Two Crore Twenty Eight Lakh Sixty One Thousand Nine Hundred & Forty Eight Only	
Quoted Rate in Figures			Less (-)	36.73%	14464753.87	INR One Crore Forty Four Lakh Sixty Four Thousand Seven Hundred & Fifty Three and Paise Eighty Seven Only	
Quoted Rate in Words		INR One Crore Forty Four Lakh Sixty Four Thousand Seven Hundred & Fifty Three and Paise Eighty Seven Only					


 9/8/10/19-3
 Executive Engineer
 HCD-10/DDA