



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशासी अभियंता / O/o Executive Engineer
उद्यान सिविल खंड-7 / Horticulture Civil Division -7
केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka
नई दिल्ली: - ११००७५ / New Delhi -110075
फोन नंबर: / Phone: 011-25086094
ईमेल - eehcd7dda@gmail.com

SPEED POST

File No. F67(1311)EE/HCD-7/DDA/2026-27/280

Dated: 08/10/26

To

Sh. Rajvir Singh
43-44A, M-Block, Gopal Nagar Phase-II,
Najafgarh, New Delhi-110043

Name of Work: M/o Completed scheme under Na-II (Horticulture Zone).
SH: Repair and Strengthening of Entrance Gate of Parks by Retrofitting of RCC Beam, Column and Slab Including Associated Finishing Works at Sector-16A (Water Body No.1), Sector-16B (Water Body No.2), Sector-15 District Park and Sector-3 (Near Balaji Apartment). Dwarka.
NIT NO.: 16/EE/HCD-7/DDA/2026-27

Dear Sir,

Your percentage rate tender for the above mentioned work is hereby accepted on behalf of the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost:	Rs 26,46,678/- (Rupees Twenty Six Lakhs Fifty Six Thousand Six Hundred Seventy Eight Only)
Quoted/Accepted Amount:	Rs. 23,67,453/- (Rupees Twenty Three Lakhs Sixty Seven Thousand Four Hundred Fifty Three Only)
Percentage:	10.55% (Ten Point Five Five percent) below the estimated cost.
DSR Applicable:	As per DSR 2023 & Market Rate.

The time allowed for execution of work shall be 60 (Sixty) Days

Please note that the time allowed for completion of work as entered in the tender shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

You are requested to attend the office of the undersigned, in person along with ID Proof, with a non-judicial stamp paper worth Rs. 100/- (Rupees One Hundred Only) within Ten days from the date of issue of this letter to sign the agreement, failing which the acceptance of tender is likely to be withdrawn and entire amount of performance guarantee shall be forfeited absolutely without any further notice.

You are requested to contact AE-I of this division and start the work at once.

The accepted schedule of rates is annexed herewith.

Er. Vishal Kumawat
EE/HCD-7

Copy to:-

- ✓ 1. SE(HCC-2)/ DDA for kind information along with Schedule of Quantities & Rates.
2. Dy. Director (System) DDA for information & with the request to kindly E-mail the same in the Website of DDA – ddatender@dda.org.in
3. Sr. AO (CAU)/Horticulture/ DDA.
4. AE (P)/HCD-7, DDA, along with Schedule of Quantities & Rates.
5. AE-I/HCD-7, DDA, along with Schedule of Quantities & Rates.
6. ASO/HCD-7 with the request to issue Register for Site/MAS Register.
7. The Labour Commissioner, 15, Rajpura Road, Delhi.
8. The Commissioner, Sales Tax, GNCTD, Room No. 211, Bikrikar Bhawan, ITO, New Delhi.
9. Income Tax Officer, Contractor Cell-I, ITO, New Delhi.
10. For Agreement.


Er. Vishal Kumawat
EE/HCD-7

Validate Print Help

status of work

Name of work: No Completed scheme under NA & B (Northculture Zone).
 Description of work: Repair and Strengthening of Entrance Gate of Pits by Retrofitting of RCC Beam, Column and Slab Including Associated Finishing Works at Sector-16A (Water Body Nos. 1), Sector-16B (Water Body Nos. 2), Sector-18 Choket Park and Sector-3 (Near Rajaji Apartment), Dwarka.

Name of the	Rajiv Singh
-------------	-------------

PRICE SCHEDULE

This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER #	NUMBER #	TOTAL AMOUNT	TEXT #
SL. No.	Item Description	Quantity	Units	Rate in Rs. p	Rs. p	In Words
1	2	3	4	5	6	7
1.00	Providing and fixing 1st quality ceramic glazed well tiles conforming to IS 15622 (thickness to be specified by the manufacturer), of approved make, in all colour, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in slating, risers of steps and dials, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 source sand) and jointing with grey cement slurry @ 3 kg/sq. m, including pointing in white cement mixed with pigment of matching shade complete.	457.00	sqm	1267.95	579483.16	[NOR] First Lath Seventy Nine Thousand Four Hundred Eighty Three and Paise Fifty Only
2.00	Demounting the work in floors and roof laid in cement mortar including sticking material within 50 mm bed. All or thickness of tiles above 25 mm and up to 40 mm	413.00	sqm	113.35	46813.66	[NOR] Forty Six Thousand Eight Hundred Fifty Three and Paise Fifty Only
3.00	Chipping of unsound/break concrete material from labra, beams, columns etc. with manual Chisel and/or by standard power driven percussion type or of approved make including uprooting of all edges, making square shoulder of concrete including cleaning the exposed concrete surface and reinforcement with wire bristles etc. and disposal of debris for all sand and lime all complete as per direction of Engineer-in-Charge	301.00	sqm	126.75	38191.73	[NOR] Thirty Eight Thousand One Hundred & Fifty One and Paise Seventy Five Only
4.00	Chemical reinforcement from roof from the reinforcing bars to give it a total rust free steel surface by using alkaline chemical rust remover of approved make with pure brash and removing loose particles after 24 hours of its application with wet brash and thoroughly washing with water and allowing it to dry, all complete as per direction of Engineer-in-Charge	719.00	sqm	8.25	5921.75	[NOR] Fifty Thousand Nine Hundred & Thirty One and Paise Seventy Five Only
5.00	a) Bars upto 12 mm diameter Providing, mixing and applying over reinforcement bars zinc silicate agent as per specification and direction of Engineer-in-Charge (Dustage / coverage as per recommendation of manufacturer) (Surface area of bars shall be measured for payment)	27.00	sqm	232.30	6272.01	[NOR] Six Thousand Two Hundred & Seventy Two and Paise Ten Only
6.00	Providing, mixing and applying bonding coat of approved adhesive on chipped portion of RCC as per specification including scaffolding and direction of Engineer-in-Charge complete in all respect. A) BBR Polymer (@ 10% of cement weight) modified commercial based coat @ 2.2 kg cement per sqm of surface area treated with specified proportion of approved polymer	301.00	sqm	93.10	28023.18	[NOR] Twenty Eight Thousand Eighty Three and Paise Ten Only
7.00	Providing, mixing and applying BBR polymer (of approved make) modified Cement mortar in proportion of 1:4 (1 cement : 4 graded coarse sand with polyene minimum 2% by wt. of cement used) as per specifications and direction of Engineer-in-Charge Note: Material and Payment. The pre-maintenance of thickness shall be done just after the surface preparation is completed and Payment under this item shall be made only after proper wet curing has been done and surface has been satisfactorily completed by sanding / tapping with a blunt metal instrument under the 75 mm size cube crushing strength at the end of 28 days to be not less than 30 N/mm ² a) 25 mm average thickness in 2 layers	301.00	sqm	583.30	174872.38	[NOR] One Lakh Seventy Nine Thousand Five Hundred & Seventy Three and Paise Thirty Only
8.00	Finishing with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. a) One or more coats on old work	104.00	sqm	102.80	10684.32	[NOR] Ten Thousand Eight Hundred & Ninety Six and Paise Eighty Only
9.00	Disposal of building rubbish / mulla / similar unserviceable, dismantled or waste materials by mechanical means including transporting, unloading in approved commercial dumping ground as approved by Engineer-in-Charge, beyond 50 m initial haul, for all loads including all lifts involved	30.00	cum	243.25	7297.50	[NOR] Seven Thousand Nine Hundred & Eighty Nine and Paise Fifty Only

③

[illegible]

(P-213)

24.00	Providing and fixing standard steel (Grade 304) railing made of hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making concavities (wherever required) and fitting the same with necessary standard steel nuts and bolts complete, i.e. fixing the railing with necessary accessories & standard steel dash fasteners, standard steel bolts etc., of required size, on the top of the flow or the side of water slab with suitable arrangement as per approval of Engineer-in-charge. (for payment purpose only weight of standard steel members shall be considered including fixing accessories such as nuts, bolts, fasteners etc.)	416.00	kg	777.40	379662.40	INR Three Lakh Twenty Nine Thousand Eighty Two and Paise Forty Only
25.00	Excavating holes upto 0.10 cum, including getting out the excavated soil, then returning the soil as deposited in layers not exceeding 20 cm in depth, including consolidating and deposited layer by ramming watering etc., disposing off surplus excavated soil as directed with in a haul of 50 mm and up to 1.5 m A) All kind of soil	1.00	Cum.	27.50	220.00	INR Two Hundred & Twenty Only
26.00	Modified Estimated Cost for Item no. 1 to 25 after using Correction Factor on DSR 2023 on account of GST @ 0.97% (i.e. Rs. 26,40,895/- (total estimated cost is to be reduced by 2.7% accordingly)	2640895.00	Rs.	-0.027	-71304.17	INR Ninety Seventy One Thousand Three Hundred & Five and Paise Eighty Three Only
27.00	Add Cost Index @ 3% on all DSR Items i.e. 2569590.00	2569590.00	Rs.	0.03	77087.70	INR Seventy Seven Thousand Eighty Seven and Paise Seventy Only
Total in Figures					2646678.00	INR Twenty Six Lakh Forty Six Thousand Six Hundred & Seventy Eight Only
Quoted Rate in Figures					2367453.47	INR Twenty Three Lakh Thirty Seven Thousand Four Hundred & Fifty Three and Paise Forty Seven Only
Quoted Rate in Words						INR Twenty Three Lakh Sixty Seven Thousand Four Hundred & Fifty Three and Paise Forty Seven Only



अधिकासी अभियन्ता

उद्यान सिविल खण्ड-7, दि.वि.प्र.

केन्द्रीय नर्सरी, सैक्टर-5

द्वारका, नई दिल्ली-110075

8/10/24



दिल्ली विकास प्राधिकरण / Delhi Development Authority
कार्यालय अधिशासी अभियंता / O/o Executive Engineer
उद्यान सिविल बंడ్-7 / Horticulture Civil Division -7

केन्द्रीय नर्सरी सेक्टर-5 द्वारका / Central Nursery, Sector -5, Dwarka

नई दिल्ली: - ११००७५ / New Delhi -110075

फोन नंबर: / Phone: 011-25086094

ईमेल - eehcd7dda@gmail.com

SPEED POST

File No. F67(1308)EE/HCD-7/DDA/2026-27/ 281

Dated: 08/10/26

To

Sh. Rajvir Singh
43-44A, M-Block, Gopal Nagar Phase-II,
Najafgarh, New Delhi-110043

Name of Work: M/o Completed scheme under Na-II (Horticulture Zone).
SH: Revival of existing Rain water harvesting structures by cleaning and replacement of filter media at various parks under the territorial jurisdiction of Hort. Civil Division-7.
NIT NO.: 13/EE/HCD-7/DDA/2026-27

Dear Sir,

Your percentage rate tender for the above mentioned work is hereby accepted on behalf of the Delhi Development Authority at the rates, terms & conditions given below:

Estimated Cost:	Rs 20,53,208/- (Rupees Twenty Lakhs Fifty Three Thousand Two Hundred Eight Only)
Quoted/Accepted Amount:	Rs. 14,46,485/- (Rupees Fourteen Lakhs Forty six Thousand Four Hundred Eighty Five Only)
Percentage:	29.55% (Twenty Nine Point Five Five percent) below the estimated cost.
DSR Applicable:	As per DSR 2023 & Market Rate.

The time allowed for execution of work shall be **45 (Forty Five) Days**

Please note that the time allowed for completion of work as entered in the tender shall be reckoned from the 10th day after the date of issue of this letter to commence the work.

You are requested to attend the office of the undersigned, in person along with ID Proof, with a non-judicial stamp paper worth Rs. 100/- (Rupees One Hundred Only) within Ten days from the date of issue of this letter to sign the agreement, failing which the acceptance of tender is likely to be withdrawn and entire amount of performance guarantee shall be forfeited absolutely without a further notice.


You are requested to contact AE-II of this division and start the work at once.

The accepted schedule of rates is annexed herewith.

Er. Vishal Kumawa
EE/HCD-7

Copy to:-

- ✓ 1. SE(HCC-2)/ DDA for kind information along with Schedule of Quantities & Rates.
2. Dy. Director (System) DDA for information & with the request to kindly E-mail the same in the Website of DDA – ddatender@dda.org.in
3. Sr. AO (CAU)/Horticulture/ DDA.
4. AE (P)/HCD-7, DDA, along with Schedule of Quantities & Rates.
5. AE-II/HCD-7, DDA, along with Schedule of Quantities & Rates.
6. ASO/HCD-7 with the request to issue Register for Site/MAS Register.
7. The Labour Commissioner, 15, Rajpura Road, Delhi.
8. The Commissioner, Sales Tax, GNCTD, Room No. 211, Bikrikar Bhawan, ITO, New Delhi.
9. Income Tax Officer, Contractor Cell-I, ITO, New Delhi.
10. For Agreement.


Er. Vishal Kumawat
EE/HCD-7

Percentage BoQ

Tender Inviting Authority: Delhi Development Authority

Name of Work: M/o completed scheme under NA-II (Horticulture Zone).

Sub Head :- Revival of existing Rain Water Harvesting structures by cleaning and replacement of filter media at various parks under the territorial jurisdiction of Horticulture Civil Division-7.

Contract No: 13/EE/HCD-7/DDA/2026-27

Name of the Bidder/ Bidding Firm / Company :		PRICE SCHEDULE						
		(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sl. No.	Item Description	NUMBER #	TEXT #	NUMBER	Rate in Rs. p	NUMBER #	TOTAL AMOUNT Rs. p	TEXT #
NUMBER #	TEXT #	Quantity	Units					TOTAL AMOUNT In Words
1	2	3	4	5	6	7		
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. (a) All kinds of soil.	214.00	sqm	34.15	7308.10	INR Seven Thousand Three Hundred & Eight and Paise Ten Only		
2	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	12.00	cum	3551.25	42815.00	INR Forty Two Thousand Six Hundred & Fifteen Only		
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	30.00	cum	2060.20	61806.00	INR Sixty One Thousand Eight Hundred & Six Only		
4	Earth work in excavation by mechanical means (Hydraulic excavator/ manual means over areas exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge. All kinds of soil	302.00	cum	177.50	53605.00	INR Fifty Three Thousand Six Hundred & Five Only		
5	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials All kinds of soil	132.00	cum	126.80	16738.00	INR Sixteen Thousand Seven Hundred & Thirty Eight Only		
6	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	176.00	sqm	54.65	9618.40	INR Nine Thousand Six Hundred & Eighteen and Paise Forty Only		
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (a) 1:5:10 (1 cement : 5 fine sand derived from natural sources: 10 graded stone aggregate 40 mm nominal size derived from natural sources)	6.00	cum	6189.65	37137.90	INR Thirty Seven Thousand One Hundred & Thirty Seven and Paise Ninety Only		

8	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in. Cement mortar 1:4 (1 cement : 4 coarse sand)	31.00	cum	7370.65	228490.15	INR Two Lakh Twenty Eight Thousand Four Hundred & Ninety and Paise Fifteen Only
9	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	120.00	sqm	425.55	51046.00	INR Fifty One Thousand & Sixty Six Only
10	Cement plaster 1:3 (1 cement: 3 coarse sand) finished with a floating coat of neat cement.	61.00	sqm	449.55	27432.86	INR Twenty Seven Thousand Four Hundred & Twenty Two and Paise Fifty Five Only
11	(a) 12 mm cement plaster Providing and fixing 100 mm thick factory made machine batched and machine mixed pre-cast R.C.C horizontal grating with frame complete as per standard design on RWH collecting chambers of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 10 mm dia TMT bars of Fe 500 grade @ maximum 100 mm c/c on both ways, neat cement punning on finished surface etc i/c cost of cartage, all leads & lift, handling at site etc all complete as per direction of Engineer-in-Charge.	19.00	sqm	4393.40	83478.00	INR Eighty Three Thousand Four Hundred & Seventy Five Only
12	Providing and fixing unplasticised Polyvinyl Chloride (UPVC) rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, having working pressure 4 Kg/cm ² including all UPVC plain fittings. This includes jointing of pipes & fittings with solvent cement, including trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work (i) Single socketed pipes (a) 200 mm dia Pipes	110.00	mt	2147.05	238178.60	INR Two Lakh Thirty Six Thousand One Hundred & Seventy Five and Paise Fifty Only
13	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm, in recharge pit, in the required thickness, for all leads & lifts, all complete as per direction of Engineer-in-charge	49.00	cum	1509.80	73980.20	INR Seventy Three Thousand Nine Hundred & Eighty and Paise Twenty Only
14	Supplying, filling, spreading & leveling gravels of size range 5 mm to 10 mm, in the recharge pit, over the existing layer of boulders, in required thickness, for all leads & lifts, all complete as per direction of Engineer in-charge	44.00	cum	1538.25	67683.00	INR Sixty Seven Thousand Six Hundred & Eighty Three Only
15	Supplying, filling, spreading & leveling coarse sand of size range 1.5 mm to 2 mm in recharge pit, in required thickness over gravel layer, for all leads & lifts, all complete as per direction of Engineer -in-charge.	44.00	cum	1538.25	67683.00	INR Sixty Seven Thousand Six Hundred & Eighty Three Only
16	Providing and laying/wrapping/fixing double-layer non-woven needle-punched geotextile membrane of 400 GSM (each layer), manufactured from continuous polypropylene/polyester fibres, having minimum thickness of 3.0 mm, minimum tear strength of 250 N (machine direction) and 215 N (cross direction) as per ASTM D4533, minimum CBR puncture strength of 1550 N as per ASTM D6241, minimum elongation at break of 57% as per ASTM D4595, Apparent Opening Size (AOS/O95) between 0.08 mm and 0.18 mm as per ASTM D4751, and minimum permittivity of 1.5 sec ⁻¹ as per ASTM D4491, including cutting, overlapping (not less than 20 cm), stitching/heat welding wherever required, laying and fixing complete, as per the manufacturer's specifications and directions of the Engineer-in-Charge. The geotextile shall possess high permeability and porosity to facilitate filtration and percolation of rainwater while preventing migration of soil particles, and shall be resistant to chemical degradation, biological degradation, ultraviolet exposure during installation, and attack by soil microorganisms. Manufacturer's original test certificate shall be submitted and approved before execution of the work.	213.00	sqm	456.80	97298.40	INR Ninety Seven Thousand Two Hundred & Ninety Eight and Paise Forty Only

17	Re-development of bore well in accordance with IS : 2800 (part 1) and IS : 11189, to maximize the inflow of water into the surrounding soil by removing silt or any other clogging material from the well, with required capacity air compressor running the compressor for required time or any suitable method approved by Engineer-in-Charge, till well is fully developed, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, including disinfection of borewell, all complete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge.	176.00	hour	1135.20	199795.20	INR One Lakh Ninety Nine Thousand Seven Hundred & Ninety Five and Paise Twenty Only
18	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per requirement, all complete for borewell of 150 mm dia	15.00	each	246.45	3696.75	INR Three Thousand Six Hundred & Ninety Six and Paise Seventy Five Only
19	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (a) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	32.00	cum	7878.50	252112.00	INR Two Lakh Fifty Two Thousand One Hundred & Twelve Only
20	Providing and placing in position 100mm thick factory made machine batched and machine mixed Precast RCC Rectangular Covers on drains of footpath of various sizes, of M-25 grade cement concrete for RCC work, including cost of centering, shuttering, reinforcement of 8mm dia TMT bars of Fe 500 grade @ maximum 100mm c/c on both ways, neat cement punning on finished surface, properly encased on all edges with 16 mm thick, 100mm wide MS sheet duly painted over priming coat, reinforcement to be welded at edges with MS sheet and providing 2 Nos. 12 mm dia bar for hooks etc 1/c cost of cartage, all leads & lift, handling at site etc. all complete as per direction of Engineer-in-Charge.	127.00	sqm	3081.95	391467.55	INR Three Lakh Ninety One Thousand Four Hundred & Seventy Five and Paise Sixty Five Only
21	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	220.00	Cum	263.95	58069.00	INR Fifty Eight Thousand & Sixty Nine Only
22	Modified Estimated Cost for item no. 1 to 21 after using Correction factor on DSR 2023 on account of GST @ 0.973 i.e. Rs.20,67,182/- (total estimated cost is to be reduced by 2.7% accordingly)	2067182.00	Rs.	-0.027	-55813.91	INR Minus Fifty Five Thousand Eight Hundred & Fourteen and Paise Nine Only
23	Add Cost Index @3% on all DSR items (except item no. 11, 12, 16 & 17) i.e. Rs. 1394625.00	1394625.00	Rs.	0.03	41938.75	INR Forty One Thousand Eight Hundred & Thirty Eight and Paise Eight Only
Total in Figures					2053208.00	INR Twenty Lakh Fifty Three Thousand Two Hundred & Eight Only
Quoted Rate In Figures					1446485.04	INR Fourteen Lakh Forty Six Thousand Four Hundred & Eighty Five and Paise Four Only
Quoted Rate In Words				Less (-)	28.56%	
		INR Fourteen Lakh Forty Six Thousand Four Hundred & Eighty Five and Paise Four Only				

Conditions :-

1. All T&P shall be arranged by the contractor.

2. In case any, Challan from MCD/NGT/Count or any other department is issued related to the subject work, the same will be solely borne by the agency.

3. All necessary permissions from any government body/DJB shall be taken by agency on its own and nothing extra shall be paid in this regards.

U. Singh
स्वांगिए

अधिकासी अभियन्ता

उद्यान सिविल खण्ड-7, दि.वि.प.

केन्द्रीय नर्सरी, सेक्टर-5

बारका. नई दिल्ली-110075

03/2

U. Singh
21-12-24