



DELHI DEVELOPMENT AUTHORITY
OFFICE THE DEPUTY DIRECTOR(HORT.)-III
B2B, JANAK PURI, NEW DELHI-110058

(011) 20896242 (E-mail id) ddahort3@dda.gov.in

No. F54 (06) DD/Hort. III/DDA/2026-27/ 667

Date: 05/8/2026

To,

M/s Raj Construction Co.,
 110 Alipur,
 Delhi 110036.

Name of work: M/o Complete Scheme under N/A-II (Hort. Zone).

M/o various Scheme under Sub-Div.-IV, Hort. Div- III, DDA,

1. Distt. Park & Lake G-17 at Paschim Vihar,
2. Park & Lake Madipur & Bhagwati Talab at Madhipur Talab
3. Distt. Part at Vishnu Garden,
4. Distt. Park Ph-I & III along with B-Block Paschim Vihar and Distt. Park RBI Office Complex at G-1 / Paschim Vihar
5. NHP at RBI Colony at G-17 Paschim Vihar,
6. NHP Raksha Kunj G-17 Paschim Vihar,
7. NHP at SBI Colony at G-17 Paschim Vihar,
8. NHP at G-17 Janmashtami Park Paschim Vihar,
9. Green Belt at PVC Market Tikkari Kalan,
10. NHP Society area south of Rohtak road, Paschim Vihar (LIC Colony),
11. NHP Society area south of Rohtak road Paschim Vihar (Ambica Vihar) &
12. Society area south of Rohtak road Paschim Vihar (Mianwali Nagar).

Sub head: - Supply and stacking of various horticulture items like good earth, jamuna sand, agro shade net, hanging baskets earthen pot, polythene bag, tuflex etc. at site.

Sir,

Your item rate tender for the above-mentioned work has been accepted on behalf of DDA at your quoted rates, terms & conditions as detailed below: -

- | | | | |
|----|-----------------------|---|---|
| 1. | Estimated Cost | : | Rs. 52,57,956/- (Rupees Fifty-Two Lakh Fifty-Seven Thousand Nine Hundred Fifty-Six Only.) |
| 2. | Tendered Amount | : | Rs.36,38,800/- (Rupees Thirty-Six Lakh Thirty-Eight Thousand Eight Hundred Only) |
| 3. | %age on Estt. Cost | : | 30.79% (below estimated cost) |
| 4. | Time allowed | : | 90 Days |
| 5. | Performance Guarantee | : | FDR/Bank Guarantee/A/C No- 86010300001646 dated 28/07/2026 Amount Rs. 8,30,463/- from Bank of Baroda RRR Center Nicholson Lines, Cariappa Marg, Delhi Cantonment, New Delhi-110010. |

You are requested to attend this office along with the non-judicial stamp paper worth Rs. 100/- to sign the formal agreement within 10(Ten) days from the date of issue of this letter, failing which the acceptance of your tender is likely to be withdrawn and earnest money deposited shall be forfeited.

You are also requested to contact **AD(H)-IV/HD-III/DDA** for taking possession of the site and starting the work at once. Please note that the time allowed (i.e., **90 Days**) for carrying out the work as entered in the tender shall be reckoned from the 10th day after the date of issue of this award letter to commence the work. Also, your letter dated **28.07.2026** shall form part of the agreement.

(Rajendra Prasad Meena)
 Dy. Director (H)/HD-III/DDA

Copy to:

1. Director (Hort.) HC-II, DDA,
2. Dy. Director (QC) III, DDA,
3. A.O. (W) II, DDA,
4. A.O. (CAU) Hort., DDA,
5. Dy. Dir. Hort. II, V, VIII & X DDA,
6. Income Tax Commr. W No. _____ New Delhi,
7. A.D.-IV/SO(T), Hort. Div. - III, DDA,
8. Comm. Sale Tax. NCT Delhi,
9. File Concern &
10. Agreement File.
11. DDA website: <https://procure.gov.in> or procureapp.org or www.dda.org

Dy. Director (H)/HD-III/DDA

Tender Inviting Authority: DELHI DEVELOPMENT AUTHORITY

Name of work: M/o Complete Scheme under N/A-II (Hort. Zone).
M/o various Scheme under Sub-Div.-IV, Hort. Div- III, DDA

Sub head: - Supply and stacking of various horticulture items like good earth, jamuna sand, agro shade net, hanging baskets earthen pot, polythene bag, tuflex etc. at site.

1. Distt. Park & Lake G-17 at Paschim Vihar
2. Park & Lake Madipur & Bhagwati Talab at Madhipur Talab
3. Distt. Part at Vishnu Garden
4. Distt. Park Ph-I & III along with B-Block Paschim Vihar and Distt. Park RBI Office Complex at G-17 Paschim Vihar
5. NHP at RBI Colony at G-17 Paschim Vihar.
6. NHP Raksha Kunj G-17 Paschim Vihar
7. NHP at SBI Colony at G-17 Paschim Vihar
8. NHP at G-17 Janmashtami Park Paschim Vihar
9. Green Belt at PVC Market Tikkari Kalan
10. NHP Society area south of Rohtak road, Paschim Vihar (LIC Colony)
11. NHP Society area south of Rohtak road Paschim Vihar (Ambica Vihar)
12. Society area south of Rohtak road Paschim Vihar (Mianwali Nagar)

NIT No.:07/DD/HD-III/DDA/2026-27

Name of the
Bidder/ Bidding
Firm / Company

M/S RAJ CONSTRUCTION CO.

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT
1	2	4	5	13	53
1 00	Supply and stacking of good earth at site including royalty and carriage upto 5km lead complete .(Good Earth measured in stacks will be reduced by 20% payment)	784 00	cum	700.00	548800.00
2 00	Supply and stacking of Jamuna Sand at site including royalty and carriage by mechanical transport and loading unloading for all lead and lift.	646 00	cum	1500.00	969000.00
3 00	Supply of Neem oil cake in 40 kg packing bag at site.	36 00	Bag	900.00	32400.00


4 01	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any with all leads and lifts (cost of manure, sludge or extra good earth if needed to be paid for separately). (a) Holes 60 cm dia., and 60 cm deep	20 00	Each	20.00	400.00
4 02	Holes 45 cm dia, and 45 cm deep	3500 00	Each	15.00	52500.00
5 00	Hiring of J.C.B/Hydraulic excavator (3-D) with driver, fuel and helper etc. for cleaning of wild growth, removal of building rubbish, debris industrial waste and refuse etc. as per direction of Engineer-in-charge	36 00	Day	6500.00	234000.00
6 00	Supply of galvanised steel barbed wire.	19 00	Qtl	5200.00	98800.00
7.00	Preparation of beds for hedging and shrubbery by excavating 60 cm deep and trenching the excavated base to a further depth of 30 cm, refilling the excavated earth after breaking clods and mixing with sludges or manure in the ratio of 8:1 (8 parts of stacked volume of earth after reduction by 20%: one part of stacked volume of sludge or manure after reduction by 8%), flooding with water, filling with earth if necessary , watering and finally fine dressing, levelling etc. including stacking and disposal of materials declared unserviceable and surplus earth by spreading and levelling as directed, within a lead of 50 m , lift up to 1.5 m complete (cost of sludge, manure or extra earth to be paid for separately).	1000.00	sqm	250.00	250000.00
8.01	Supply of trees plants Providing and stacking of Butea frondosa (Flame of forest) height 60- 75 cm. in polybag of size 25 cm as per direction of the officer-in-charge.	20 00	Each	50.00	1000.00
9.01	Supply of Shrubs Plants Providing and stacking of Largerstroemia indica of height 45-60 cm. in polybag of size 20 cm as per direction of the officer-in-charge.	600.00	Each	40.00	24000.00
9 02	Providing and stacking of Tecoma gaudichaudi of height 60-75cm. With 5-6 branched in polybag of size 25 cm as per direction of the officer-in-charge.	2500.00	Each	30.00	75000.00
9 03	Providing and stacking of Calliandra hybrida of height 75-90 cm. With 4-5 branched in polybag of size 25 cm as per direction of the officer-in-charge.	400.00	Each	30.00	12000.00
9 04	Providing and stacking of Hamelia patens of height 60-75 cm. with 6-8 branches in poly bag of size 25 cm as per direction of the officer-incharge.	1000 00	Each	20.00	20000.00
9.05	Providing and stacking of Tabernaemontana coronaria (Chandni single) variegated of height 60-75 cm., 5 6 branches in p bag of size 25 cm as per direction of the officer-in-charge.	2000 00	Each	20.00	40000.00

10.01	Supply of Hedge Plants: Providing and stacking of <i>Murraya koenigii</i> of height 45-60 cm. in polybag of size 15 cm as per direction of the officer-in-charge	7000.00	Each	15.00	105000.00
10.02	Providing and stacking of <i>Putranjiva roxburghii</i> of height 45-60 cm. in polybag of size 15 cm as per direction of the officer-in-charge.	2500.00	Each	15.00	37500.00
10.03	Providing and stacking of <i>Putranjiva roxburghii</i> of ht. 60-75 cm in bag of size 20 cm as per direction of the officer-in-charge.	5000.00	Each	15.00	75000.00
11.01	Supply of ground cover plants Providing and stacking <i>Iresine herbstii</i> , of height 25 cm to 30 cm size in polythene bag.	2000.00	Each	8.00	16000.00
11.02	Providing and stacking <i>Ophiopogon</i> , Green/Black full of leaves in 15 cm in polythene bag.	2000.00	each	10.00	20000.00
11.03	Providing and stacking <i>Ophiopogon jaburan</i> (variegated), full of variegated leaves in 15 cm size in polythene bag.	2000.00	Each	10.00	20000.00
11.04	Providing and stacking <i>Syngonium</i> (Butterfly) variegated with 2 to 3 suckers healthy foliage in in polythene bag.	2000.00	each	5.00	10000.00
11.05	Providing and stacking <i>Tradescantia</i> , full of leaves in polythene bag	2000.00	Each	5.00	10000.00
11.06	Providing and stacking of <i>Ophiopogon</i> , Green/ Black full of leave in 15 cm size of polybag and as per direction of the officer-in-charge.	2000.00	Each	5.00	10000.00
12.00	Providing and fixing of Tuflex Garden fencing Hexagonal net/or equivalent of green colour having contents (Weight grams/sqm. 510 (+/- 8%)) in width of 60 cm. with bamboo of 90 cm. length. The bamboo should be painted with green colour paint of approved brand and manufacture (two or more coats) and fixed 30 cm. below ground level and 60 cm. above ground level at a distance of 1.50 mtrs. The net and bamboo should be binded with 2 mm. G.I. Wire at three places properly as per direction of Engineer-in-charge.	2930.00	Per Sqm	90.00	263700.00
13.00	Supply of best quality Agro shade net green color (50m x 3m) 75:25 (Sunshade) ratio in each Bundle as per direction of Engineer-in-office.	10.00	sqm	20.00	200.00
14.00	Provision of cocopit	100.00	Bricks	150.00	15000.00
15.00	Supply of Moss Stick ht. 3 feet at site.	100.00	Each	40.00	4000.00

16.00	Supply of Moss Grass at site.	100.00	Per Kg	40.00	4000.00
17.01	Supply of polythene bags Supply of polythene bags size 5"x7"(gauge 220) both layer at site	500.00	kg	150.00	75000.00
17.02	Supply of polythene bags size 6"x8"(gauge 175) both layer at site	200.00	Kg	150.00	30000.00
17.03	Supply of polythene bags size 6"x9" both layer at site	300.00	Kg	150.00	45000.00
18.01	Provision of earthen pots (empty) only for seed bed/nursery: Supply of empty earthen pots at site. Top inside dia 30 cm, outer bottom dia 20 cm, 30 cm perpendicular height size 12"(S.P) at site.	500.00	Each	50.00	25000.00
18.02	Supply of empty earthen pots at site. Top inside dia 25 cm outer bottom dia 15 cm. 25 cm perpendicular height size 10" (S.P) at site.	1000.00	Each	30.00	30000.00
18.03	Supply of empty earthen pots at site. Top inside dia 20 cm outer bottom dia 10 cm. 20 cm perpendicular height size 8" (S.P) at site.	1000.00	Each	20.00	20000.00
19.00	Providing square cement concrete pots of specified size, cast with cement concrete of nominal mix 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 6 mm nominal size), reinforced with 7 Nos. (3 nos horizontal & 4 nos vertical " U: shape) M.S. wires of 3.5 mm dia as per design, including required form work, finishing with cement punning on exposed surface, curing for specified period and stacking in required rows& height, all complete as per direction of office-in-charge Top inner width 35 cm, outer bottom width 25 cm, total height 35 cm and wall thickness 25.4mm.	50.00	Each	300.00	15000.00
20.01	Provision of Plastic Hanging Basket Supply of Plastic Hanging Basket Size 9"	100.00	Each	150.00	15000.00
20.02	Supply of Plastic Hanging Basket Size 7"	100.00	Each	150.00	15000.00
21.01	Provision of Annual Flower Seedlings/cutting. Supplying and Stacking of winter seasonal seedling/cutting at site of work well developed and healthy free from disease in pro tray and each pro tray having 100 Nos plants. Antirrhinum Dwarf	5.00	Each	500.00	2500.00
21.02	Aster Dwarf	5.00	Each	500.00	2500.00
21.03	Carnation (Double) Dutch	5.00	Each	500.00	2500.00

21 04	Chrysanthemum Double	5 00	Each	500.00	2500.00
21 05	Dahlia Double	5 00	Each	500.00	2500.00
21 06	Dianthus Hybrid	5 00	Each	500.00	2500.00
21 07	Gazania hybrid	5.00	Each	500.00	2500.00
21.08	Gerbera hybrid double	5.00	Each	500.00	2500.00
21.09	Marigold french hybrid dwarf	5.00	Each	500.00	2500.00
21 10	Marigold inca hybrid	5 00	Each	500.00	2500.00
21 11	Pansy hybrid	5 00	Each	500.00	2500.00
21.12	Petunia hybrid	5 00	Each	500.00	2500.00
21 13	Salvia hybrid different colour	5 00	Each	500.00	2500.00
21 14	Verbena hybrid	5 00	Each	500.00	2500.00
22 01	Provision of Oranamental plants: Providing and stacking of Acalypha Different colour well developed, fresh & healthy with good foliage, multi branch 30 cm to 45 cm ht. plant in polythene bag.	500 00	Each	20.00	10000.00
22 02	Providing and stacking of Bougainvillea named variety. Sobhra. Thima. Marry palmar, Cherry Blossom etc. well developed with fresh & healthy bushy plant in full bloom 75 cm to 90 cm ht. plant in polythene bag	500 00	Each	30.00	15000.00
22 03	Providing and stacking of Foxtail palm well developed with fresh & healthy foliage of ht. plant 210 cm to 240 cm in polythene bag.	100 00	Each	900.00	90000.00

22.04	Providing and stacking of Ixora singaporensis different colour having 30 cm and above ht., well developed with fresh & healthy foliage with bloom in polythene bag.	500.00	Each	50.00	25000.00
23.01	Supply of Foliage & Shade Loving Providing and stacking of Areca Palm having ht. 90 cm to 1.20 m with 4 to 5 suckers, well developed, fresh and healthy with lush green foliage in polythene bag.	500.00	Each	90.00	45000.00
23.02	Providing and stacking of Croton baby golden variety having ht. 30 cm and above, well developed with full of fresh and healthy leaves in polythene bag.	500.00	Each	90.00	45000.00
23.03	Providing and stacking of Dieffenbachia Tropic-snow having ht. 60 cm & above with 8-10 leaves, well developed, fresh & healthy in polythene bag.	500.00	Each	90.00	45000.00
23.04	Providing and stacking of Dracaena Kedarnath having ht. 30 cm & above, well developed with good colorful foliage in polythene bag.	500.00	Each	60.00	30000.00
23.05	Providing and stacking of Dracaena Mahatma having ht. 30 cm to 45 cm, well developed, fresh and healthy foliage in polythene bag.	500.00	Each	60.00	30000.00
23.06	Providing and stacking of Dracaena Victoria having ht. 30 cm & above, well developed with full of leaves, fresh and healthy in polythene bag.	500.00	Each	60.00	30000.00
23.07	Providing and stacking of Livistona Palm having ht. 60 cm to 75 cm, well developed with 8 to 10 leaves, fresh & healthy foliage in polythene bag.	500.00	Each	11.00	5500.00
23.08	Providing and stacking of Phoenix Palm having ht. 75 cm to 90 cm with 10 to 15 leaves, well developed, fresh and healthy in polythene bag.	100.00	Each	50.00	5000.00
23.09	Providing and stacking of Sanchezia Nobili's having ht. 30 cm & above, well developed with fresh & healthy foliage in polythene bag.	500.00	Each	20.00	10000.00
Total in Figures					3638800
Quoted Rate in Words		INR Thirty Six Lakh Thirty Eight Thousand			


 Dy. Director (Hort.)
 Hort. Division-3
 D.D.A.

Delhi Development Authority
Terms & Conditions

Name of work: M/o Complete Scheme under N/A-II (Hort. Zone).

M/o various Scheme under Sub-Div.-IV, Hort. Div- III, DDA

Sub head: - **Supply and stacking of various horticulture items like good earth, jamuna sand, agro shade net, hanging baskets earthen pot, polythene bag, tuflex etc. at site.**

1. Distt. Park & Lake G-17 at Paschim Vihar
2. Park & Lake Madipur & Bhagwati Talab at Madhipur Talab
3. Distt. Part at Vishnu Garden
4. Distt. Park Ph-I & III along with B-Block Paschim Vihar and Distt. Park RBI Office Complex at G-17 Paschim Vihar
5. NHP at RBI Colony at G-17 Paschim Vihar.
6. NHP Raksha Kunj G-17 Paschim Vihar
7. NHP at SBI Colony at G-17 Paschim Vihar
8. NHP at G-17 Janmashtami Park Paschim Vihar
9. Green Belt at PVC Market Tikkari Kalan
10. NHP Society area south of Rohtak road, Paschim Vihar (LIC Colony)
11. NHP Society area south of Rohtak road Paschim Vihar (Ambica Vihar)
12. Society area south of Rohtak road Paschim Vihar (Mianwali Nagar)

1. The work shall be executed as per CPWD specification.
2. No T & P shall be issued to the contractor by the department against this work.
3. The rates should be quoted in both figures and words including all taxes.
4. The plants should be healthy and free from any kind of diseases.
5. The undersigned reserved the right to reject all or even lowest tender without assigning any reason.
6. If any causality occurs, the same shall be replaced within 7 days by the same specification and same nomenclature by the contractor at his own cost.
7. DDA is not responsible for any litigation with labour in Court of Law & contractor will settle the matter on his own risk & cost.
8. DDA will not pay any compensation to the labour of any miss-happening occurred during the execution of work.
9. If any material is rejected or work found defective, the same shall be removed/rectified by the contractor within one week failing which the same shall be removed/rectified by the department & cost will be recovered from the agency as approved by the Competent Authority.
10. The quantity can be increased or decreased as per actual requirement at site,
11. No minus deviation allowed if found that same the recovery would be done at justified rate.
12. The instructions of the department staff has to be carried over properly. In case of any difference of opinion/interpretation of specification and condition the matter shall be referred by the contractor to the Officer-in-Charge for his decision which shall be final and binding.
13. All incident charge of any kind whatsoever including cartage, storage, cutting and wastage etc. shall be born exclusively by the contractor and no claim to be entertained to this effect.
14. The contractor must be available at site of work whenever officer -in-charge visits the site,
15. The departmental instruction issued from time to time will also be applicable.
16. The measurement of all the items should be done through E-Measurement.
17. The work should be completed within stipulated period.
18. The pH value of good earth should be got tested trough certified Govt. laboratory by the contractor own his cost.
19. The materials like, earth, good earth, etc. should be free from Kankar, pathar, polythene etc.

A-----
C-----
CS-----
O/V-----
D-----

