



OFFICE OF THE EXECUTIVE ENGINEER
HORTICULTURE CIVIL DIVISION NO.10
D.D.A., SCHOOL BLOCK, SHAKARPUR,
DELHI - 110092 (E-mail: eehcdx@gmail.com)

No. F.1 (39)2023-2024/A/cs/HCD-10/DDA/714

Dated: 18/07/23

To,

Sh. Aditya
E-46/A, West Jyoti Nagar
Shahdara, Delhi -110094
E-mail: adityajangid1994@gmail.com
M.No.: 9999069088

Name of work: **M/O Competed Scheme under NA-II Hort. Zone.)**
SH: Repair of Walkways, Parking area, Fencing etc. at Asita West
(Golden Jubilee Park).Park, Phase-II.
NIT No. : 05/EE/HCD-10/DDA/2023-2024
Estimated cost: Rs.94,63,575/-

Dear Sir(s),

Your percentage rate tender for the above mentioned work has been accepted on behalf of Delhi Development Authority at your quoted rates subject to following terms & condition:-

1.	Estimated Cost	Rs. 94,63,575/- (Rupees Ninety Four Lakh Sixty Three Thousand Five Hundred Seventy Five only)
2.	Quoted & Accepted Rate	(-) 46.46% below on the Estimated Cost.
3.	Quoted Tender Amount	Rs.50,66,798/- (Fifty Lakh Sixty Six Thousand Seven Hundred Ninety Eight Only)
4.	Accepted Tender Amount	Rs.50,66,798/- (Fifty Lakh Sixty Six Thousand Seven Hundred Ninety Eight Only)

Time allowed for carrying out the work shall **75 Days** only. You are requested to contact A.E.-V/ HCD-10 / DDA of this division and start the work immediately.

You are requested to attend this office for drawing formal agreement along with a non-judicial stamp paper worth Rs.100/- (Rs. One hundred only) which shall be brought by you within 15 days after issue of this letter, failing which the acceptance of the work is likely to be withdrawn.

Please note that the time allowed for carrying out the work as entered in the tender will be reckoned from 10th day after the date of issue of this letter to commence the work.

Thanking you,

Yours Faithfully


(Bhupendra Kumar)
Executive Engineer
HCD-10/D.D.A.

Valid
Tender Inviting
Name of Work: M/C
SH:- Repair of Wall
NIT No: 05/EE/H

Name of
the Bidder/
Bidding
Firm

Copy to:-

1. C.E.(Hort.)/D.D.A.
2. S.E./HCC-3/D.D.A.
3. F.O. to C.E. (Hort.), D.D.A.
4. All EE's/ Hort. Zone/DDA
5. E.E. (QAC)-VI/D.D.A., Vikas Sadan, New Delhi - 110023.
6. Sr. A.O./CAU(Hort.)/ D.D.A.
7. AE(QC) to CE(Hort.)/DDA Vikas Minar, New Delhi-110002.
8. Labour Commissioner, 15, Rajpura Road, Delhi
9. Income Tax Office (contractor circle), Ward 38(3), Civic Centre, Minto Road, New Delhi.
10. Secy., DDA Contractor Association (Regd.) Vikas Kuteer, New Delhi.
11. DDA Contractor Welfare Association (Regd) Vikas Kuteer, New Delhi.
12. Secy. DDA Contractor Registration Board, Vikas Minar, New Delhi.
13. T.Y.A.DDA Contractor Association, 11-12, Vir Sawarkar Block, Budh Bazar, Gandhi Nagar, Delhi-31.
14. Delhi Contractor & Building Association (Regd.), 306, Masjid Moth, Rai Sahib Mkt., South Extn. Pt-II, N.D.-49.
15. AE-V/HCD-10/D.D.A. with the direction to hand over the site the contractor and ensure timely start the work.
16. A.E.(P)HCD-10/D.D.A.
17. Head Clerk, A.A.O., /HCD-10/D.D.A.
18. Agreement copy.


18/07/23
Executive Engineer
HCD-10/D.D.A.

Percentage BoQ

Order Inviting Authority: Delhi Development Authority

Name of Work: M/O various schemes under Nazul A/C-II (East Zone)

Work: Repair of Walkways, Parking area, Fencing etc. at Asita West (Golden Jubilee park).

No: 05/EE/HCD-10/DDA/2023-24

Name of Bidder/

Address

City

State

Pin Code

Phone No.

E-mail

Signature

Date

Place

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)


NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
SL No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	18.00	cum	218.60	3935	INR Three Thousand Nine Hundred & Thirty Five Only
2	Excavating holes more than 0.10 cum & upto 0.5 cum including getting out the excavated soil, then returning the soil as required in layers not exceeding 20cm in depth, including consolidating each deposited layer by ramming, watering etc, disposing of surplus excavated soil, as directed within a lead of 50 m and lift upto 1.5 m. All kinds of soil	1230.00	each	69.40	85362	INR Eighty Five Thousand Three Hundred & Sixty Two Only
3	Taking out existing kerb stones of all types from footpath/ central verge, including removal of mortar etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	1500.00	metre	32.40	48600	INR Forty Eight Thousand Six Hundred Only
4	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	215.00	sqm	108.65	23360	INR Twenty Three Thousand Three Hundred & Sixty Only
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size)	36.00	cum	5660.45	203776	INR Two Lakh Three Thousand Seven Hundred & Seventy Six Only

6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	348.00	cum	6833.40	2378023	INR Twenty Three Lakh Seventy Thousand & Twenty Three Only
7	Laying at or near ground level old kerb stones of all types in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints, except at sharp curve, shall not be more than 5 mm), including making drainage opening wherever required etc. complete as per direction of Engineer-in-charge. (Length of finished kerb edging shall be measured for payment). (Old kerb stones shall be supplied by the department free of cost)	500.00	metre	90.85	45425	INR Forty Five Thousand Four Hundred & Twenty Five Only
8	Providing and laying at or near ground level factory made kerb stone of M-25 grade cement concrete in position to the required line, level and curvature, jointed with cement mortar 1:3 (1 cement : 3 coarse sand), including making joints with or without grooves (thickness of joints except at sharp curve shall not to more than 5mm), including making drainage opening wherever required complete etc. as per direction of Engineer-in-charge (length of finished kerb edging shall be measured for payment). (Precast C. C. kerb stone shall be approved by Engineer-in-charge).	45.00	cum	8613.55	387610	INR Three Lakh Eighty Seven Thousand Six Hundred & Ten Only
9	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	131.00	sqm	951.00	124581	INR One Lakh Twenty Four Thousand Five Hundred & Eighty One Only
10	Providing and laying 60mm thick factory made cement concrete Grass paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per the direction of Engineer-in-charge.	84.00	sqm	1025.40	86134	INR Eighty Six Thousand One Hundred & Thirty Four Only
11	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	138.00	KG	111.95	15449	INR Fifteen Thousand Four Hundred & Forty Nine Only
12	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	326.00	KG	612.25	199594	INR One Lakh Ninety Nine Thousand Five Hundred & Ninety Four Only
13	Supplying and stacking at site. Moorum	270.00	cum	888.30	239841	INR Two Lakh Thirty Nine Thousand Eight Hundred & Forty One Only

14
Lakh Seventy
31 Three Only

14	Spreading MOORUM/ JAMUNA SAND w/c watering, rolling and preparation of surface having thickness 50mm or required as per site condition and as per direction of Engineer-in-charge (The cost of material shall be paid separately).	270.00	cum	215.40	58168	INR Fifty Eight Thousand One Hundred & Fifty Eight Only
15	Supplying at site : R.C.C. post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-in-charge (cost of earth works in excavation, concrete works in foundation to be paid separately).	133.00	cum	29105.40	3871018	INR Thirty Eight Lakh Seventy One Thousand & Eighteen Only
16	Fencing with RCC Posts placed at required distance, embedded in Cement Concrete block every 15th post, last but one end post and corner post shall be struttred on both side and end posts one side only. Provided with horizontal line and two diagonals of Reinforced Barbed Tape (RBT) of high tensile strength of 165 kg./sqmm.. with tape 0.52 mm thick and weight 43.478 gm. per meter between the two posts fitted and fixed with G.I. Staples on wodden plugs or G.I. binding wire tied to 6mm bar nibs fixed while casting the posts (costs of RCC Posts, Struts, Earth Work and Concrete to be paid separately) : Payment to be made per meter cost of total length of reinforce barbed tape (RBT) used.	52921.00	metre	15.80	836152	INR Eight Lakh Thirty Six Thousand One Hundred & Fifty Two Only
17	Making bajri path including preparation of sub grade, supplying and laying brick aggregate of 50 mm nominal size 7.5 cm deep with blinding material consisting of 12 mm moorum and 12 mm red bajri consolidated with road roller.	150.00	sqm	185.65	27878	INR Twenty Seven Thousand Eight Hundred & Seventy Eight Only
18	Providing and fixing 10x10x7.50 cm Granite stone block hand cut and chisel dressed on top, for paving in floors, drains etc. laid over 20mm thick base mortar 1:4 (1 cement : 4 coarse sand) with joints 10mm wide filled with same mortar including ruled pointing etc. complete as per direction of engineer-in-charge.	52.00	sqm	1871.80	97334	INR Ninety Seven Thousand Three Hundred & Thirty Four Only
19	Manufacturing, supplying and fixing retro reflective overhead signage boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity and encapsulated lens type heat activated retro reflective sheeting conforming to type - III of ASTM-D-4956-01 as approved by Engineer-in-charge, letters, borders etc. as per IRC : 67-2001 in silver white with blue colour back ground and with high intensity grade, pasted on substrate by pressure sensitive adhesive backing which shall be activated by applying plate of structural frame work by means of suitable sized aluminium alloys, rivets or bolts & nuts @ 300 mm centre to centre all along the periphery as well as in two vertical rows along with theft resistant measures, including the cost of painting with two or more coats of epoxy paint in grey colour on the back side of aluminium sheet including appropriate priming coat. The rate includes the cost of rounding off the corners, lowering down the structural frame work from the gantry, fixing and erecting the same in position all complete as per drawings, specification and direction of the engineer-in-charge. (Structural frame work including M.S. plate to be provided separately. Rectangular area of the sheet only shall be measured for payment). a) Overhead informatory road signage	2.00	sqm	5609.55	11219	INR Eleven Thousand Two Hundred & Nineteen Only

20	Providing and laying matt finished vitrified tile of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS: 15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	15.00	sqm	1250.75	18761	INR Eighteen Thousand Seven Hundred & Sixty One Only
21	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work.	4.00	sqm	131.45	526	INR Five Hundred & Twenty Six Only
22	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : a) One or more coats on old work	200.00	Sqm	86.55	17310	INR Seventeen Thousand Three Hundred & Ten Only
23	Welding by gas or electric plant including transportation of plant at site etc. complete.	200.00	cm	3.40	680	INR Six Hundred & Eighty Only
24	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	35.00	cum	219.35	7677	INR Seven Thousand Six Hundred & Seventy Seven Only
25	Providing and fixing self adhesive vinyl sheet pasted on 3 mm ACP sheet as approved by Engineer-in-charge.	10.00	sqm	4222.05	42221	INR Forty Two Thousand Two Hundred & Twenty One Only
26	Providing and placing RCC GARDEN BENCHES with arm-rest of required size etc. complete in all respect at site as approved and as per direction of Engineer in Charge	15.00	each	9247.15	138707	INR One Lakh Thirty Eight Thousand Seven Hundred & Seven Only
	Add GST factor (0.0633) on items except item no. 10,14,16,25 & 26				494244	INR Four Lakh Ninety Four Thousand Two Hundred & Forty Four Only
Total in Figures					9463575.00	INR Ninety Four Lakh Sixty Three Thousand Five Hundred & Seventy Five Only
Quoted Rate in Figures						
					Less (-)	46.46%
Quoted Rate in Words					5066798.06	INR Fifty Lakh Sixty Six Thousand Seven Hundred & Ninety Eight and Paise Six Only
INR Fifty Lakh Sixty Six Thousand Seven Hundred & Ninety Eight and Paise Six Only						


 19/10/23
 Executive Engineer
 HCD-10/DDA